# Appendix A

# Applicable Campus Master Plan EIR Mitigation Measures

# APPLICABLE MASTER PLAN EIR MITIGATION MEASURES

The mitigation measures identified in the Master Plan EIR which are applicable to and incorporated into the project are listed below for reference.

# MITIGATION MEASURES IDENTIFIED IN THE MASTER PLAN EIR THAT ARE APPLICABLE TO THE PROJECT

# **Mitigation Measures**

# **AESTHETICS**

### 3.1-3a: Use Nonreflective Materials on Building Surfaces

Cal Poly shall require the use of nonreflective exterior surfaces and nonreflective (mirrored) glass for all new or redeveloped structures.

### 3.1-3c: Use Directional Lighting for Campus Development

Cal Poly shall require all new, permanent outdoor lighting fixtures to utilize directional lighting methods (e.g., shielding and/or cutoff-type light fixtures) to minimize glare and light spillover onto adjacent structures. In addition, light placement and orientation shall also be considered such that light spillover is reduced at nearby land uses, to the extent feasible. Verification of inclusion in project design shall be provided at the time of design review

# AIR QUALITY

### 3.3-2: Implement Dust and Exhaust Emissions Reduction Measures

Based on the APCD CEQA Handbook, Cal Poly shall ensure that construction contractors implement the following measures for all 2035 Master Plan development:

#### Standard Construction Emission Reduction Measures for All Projects

- Staging and queuing areas or diesel idling associated with equipment used during construction of new/renovated buildings on campus shall not be located within 1,000 feet of sensitive receptors. This distance can be adjusted if it can be demonstrated to Cal Poly by the construction contractor, with substantial evidence, that risk levels at nearby receptors would not exceed an estimated risk of 10 chances in a million.
- Off-road diesel equipment shall comply with the 5-minute idling restriction identified in Section 2449(d)(3) of CARB's In-Use Off-Road Diesel regulation.
- Signs shall be posted in the designated queuing areas and job sites to remind offroad equipment operators of the 5-minute idling limit.
- ▶ Reduce the amount of the disturbed area where possible.
- ► Use of water trucks or sprinkler systems in sufficient quantities to prevent airborne dust from leaving the site and from exceeding the APCD's limit of 20 percent opacity for greater than 3 minutes in any 60-minute period. Increasing watering frequency would be required whenever wind speeds exceed 15 miles per hour. Reclaimed (non-potable) water should be used whenever possible. Please note that during drought conditions, water use may be a concern and the contractor or building shall consider the use of an APCD-approved dust suppressant where feasible to reduce the amount of water used for dust control.

- All dirt stockpile areas shall be sprayed daily as needed.
- Permanent dust control measures identified in the approved project revegetation and landscape plans shall be implemented as soon as possible following the completion of any soil disturbing activities.
- Exposed ground areas that are planned to be reworked at dates greater than one month after initial grading will be sown with fast germinating, non-invasive grass seed and watered until vegetation is established.
- ► All disturbed soil areas not subject to revegetation shall be stabilized using approved chemical soil binders, jute netting, or other methods approved in advance by APCD.
- ► All roadways, driveways, sidewalks, etc. to be paved shall be completed as soon as possible. In addition, building pads shall be laid as soon as possible after grading unless seeding or soil binders are used.
- Vehicle speed for all construction vehicles shall not exceed 15 mph on any unpaved surface at the construction site.
- All trucks hauling dirt, sand, soil, or other loose materials shall be covered or should maintain at least two feet of freeboard (minimum vertical distance between top of load and top of trailer) in accordance with CVC Section 23114.
- ► Install wheel washers where vehicles enter and exit unpaved roads onto streets or wash off trucks and equipment leaving the site. "Track-Out" is defined as sand or soil that adheres to and/or agglomerates on the exterior surfaces of motor vehicles and/or equipment (including tires) that may then fall onto any highway or street as described in California Vehicle Code Section 23113 and California Water Code 13304. To prevent Track Out, designate access points and require all employees, subcontractors, and others to use them. Install and operate a "trackout prevention device" where vehicles enter and exit unpaved roads onto paved streets. The track-out prevention device can be any device or combination of devices that are effective at preventing track out, located at the point of intersection of an unpaved area and a paved road. Rumble strips or steel plate devices require periodic cleaning to be effective. If paved roadways accumulate tracked out soils, the track-out prevention device may need to be modified.
- Sweep streets at the end of each day if visible soil material is carried onto adjacent paved roads. Water sweepers with reclaimed water should be used where feasible.
- ▶ All of these fugitive dust mitigation measures shall be included on grading and building plans.
- ▶ Maintain all construction equipment in proper tune according to manufacturer's specifications.
- ► Fuel all off-road and portable diesel-powered equipment with CARB-certified motor vehicle diesel fuel (non-taxed version suitable for use off-road).
- Electrify equipment when feasible.
- ► Substitute gasoline-powered in place of diesel-powered equipment, where feasible.
- All architectural coatings (e.g., paint) used in project buildings and parking areas will not exceed a volatile organic compound content of 50 grams per liter.
- ► Use diesel construction equipment meeting CARB's Tier 2 certified engines or cleaner off-road heavy-duty diesel engines and comply with the State Off-Road Regulation.
- ► Use on-road heavy-duty trucks that meet the CARB's 2007 or cleaner certification standard for on-road heavyduty diesel engines and comply with the State OnRoad Regulation.
- Construction or trucking companies with fleets that that do not have engines in their fleet that meet the engine standards identified in the above two measures (e.g. captive or NOx exempt area fleets) may be eligible by proving alternative compliance.
- ► Use alternatively fueled construction equipment on-site where feasible, such as compressed natural gas (CNG), liquefied natural gas (LNG), propane or biodiesel.

For individual projects proposed under the 2035 Master Plan, APCD screening criteria (rather than emissions modeling) shall be applied to determine if emissions from the project would be below the adopted numeric thresholds. If an individual project would exceed the screening criteria, project-specific emissions modeling shall be conducted to determine if APCD's adopted numeric project-level thresholds would be exceeded. If emissions modeling demonstrates that the individual project's operational emissions would exceed the APCD thresholds, the following mitigation measures would apply in addition to the Standard Construction Emission Reduction Measures described above.

Enhanced Construction Emission Reduction Measures for Individual Projects that Exceed APCD Thresholds

- Implement Best Available Control Technologies (BACT) and a Dust Control Management Plan that encompasses all, but is not limited to, dust control measures that were listed above in the "Standard" measures section;
- ▶ further reducing emissions by expanding use of Tier 3 and Tier 4 off-road and 2010 on-road compliant engines;
- repowering equipment with the cleanest engines available;
- ▶ installing California Verified Diesel Emission Control Strategies, listed at arb.ca.gov/diesel/verdev/vt/cvt.htm; tabulation of on- and off-road construction equipment (age, horsepower, miles, and/or hours of operation);
- ▶ schedule of construction truck trips during non-peak hours to reduce peak hour emissions;
- ▶ limit the length of the construction work day period, if necessary; and
- ▶ phase construction activities, if appropriate.

### 3.3-3a: Implement Mitigation Measure 3.8-1

Cal Poly will incorporate the mitigation listed under Mitigation Measure 3.8-1 of Section 3.8, "Greenhouse Gas Emissions," to reduce operational emissions of criteria air pollutants and ozone precursors to the extent feasible.

### 3.3-3b: Reduce Operational Emissions

The following measures shall be implemented, where appropriate, to reduce operational emissions of ozone precursors to levels below the APCD-adopted thresholds. This list is not exhaustive and other or alternative emission reduction measures shall be considered and implemented based on new technologies and as APCD operational air quality mitigation measures are further developed over the life of the Master Plan. The following APCD-recommended measures would apply to new land use development within the 2035 Master Plan area:

- ► All existing landscaping equipment (e.g., lawnmowers, leaf blowers, chainsaws), upon time of replacement, will be replaced with electric ones. All new landscaping equipment purchased will be electric.
- All architectural coatings (e.g., paint) used in project buildings and parking areas will not exceed a volatile organic compound content of 50 grams per liter.
- Exceed CALGreen standards by 25 percent for providing on-site bicycle parking; both short-term racks and long-term lockers, or a locked room with standard racks and access limited to bicyclist only.
- ▶ Implement a "No Idling" vehicle program which includes signage, enforcement, etc.
- ▶ Provide shade over 50 percent of parking spaces to reduce evaporative emissions from parked vehicles.

For individual projects that are determined to exceed applicable APCD thresholds, after incorporation of all available/applicable onsite measures, the following may be considered:

- ▶ Incorporate additional off-site mitigation (e.g., emissions offsets pursuant to APCD rules and regulations).
- Prepare an operational activity management plan that demonstrates how individual project impacts would be reduced to a level of insignificance. Specific measures may include onsite and offsite mitigation strategies, including the scheduling of activities during off-peak hours and the purchase of mitigation offsets.

# ARCHAEOLOGICAL, HISTORICAL AND TRIBAL CULTURAL RESOURCES

# 3.4-2a: Identify and Protect Unknown Archaeological Resources

During project-specific environmental review of development under the 2035 Master Plan, Cal Poly shall define each project's area of effect for archaeological resources in consultation with a qualified archaeologist, as defined by the Secretary of Interior. The University shall determine the potential for the project to result in cultural resource impacts, based on the extent of ground disturbance and site modification anticipated for the project. Cal Poly shall determine the level of archaeological investigation that is appropriate for the project site and activity, as follows:

- ► Minimum: excavation less than 18 inches deep and less than 5,000 square feet of disturbance (e.g., a trench for lawn irrigation, tree planting). Implement Mitigation Measure 3.4-2a(1).
- Moderate: excavation below 18 inches deep and/or over a large area on any site that has not been characterized as sensitive and is not suspected to be a likely location for archaeological resources. Implement Mitigation Measure 3.4-2a(1) and (2).
- ► Intensive: excavation below 18 inches and/or over a large area on any site that is within the zone of archaeological sensitivity, i.e., within 750 feet, along Brizzolara Creek or Stenner/Old Garden Creek (as shown in Figure 3.4-1) or that is adjacent to a recorded archaeological site. Implement Mitigation Measure 3.4-2a(1), (2), and (3).

Cal Poly shall implement the following steps to identify and protect archaeological resources that may be present in the project's area of effects:

- 1. For project sites at all levels of investigation, contractor crews shall be required to attend a training session before the start of earth moving, regarding how to recognize archaeological sites and artifacts and what steps shall be taken to avoid impacts to those sites and artifacts. In addition, campus employees whose work routinely involves disturbing the soil shall be informed how to recognize evidence of potential archaeological sites and artifacts. Before disturbing the soil, contractors shall be notified that they are required to watch for potential archaeological sites and artifacts and to notify Cal Poly Facilities Management and Development if any are found. A qualified archeologist would be present onsite during earth-moving activities to provide oversight to contractor crew and campus employees. In the event of a find, Cal Poly shall implement item (5), below.
- 2. For project sites requiring a moderate or intensive level of investigation, a surface survey shall be conducted by a qualified archaeologist once the area of ground disturbance has been identified and before soil disturbing activities. For sites requiring moderate investigation, in the event of a surface find, intensive investigation shall be implemented, as per item (3), below. Irrespective of findings, the qualified archaeologist shall, in consultation with Cal Poly Facilities Management and Development, develop an archaeological monitoring plan to be implemented during the construction phase of the project. If the project site is located within a zone of archaeological sensitivity (i.e., within 750 feet of Brizzolara Creek, Stenner Creek, or Old Garden Creek) or it is recommended by the archaeologists, Cal Poly shall notify the appropriate Native American tribe and extend an invitation for monitoring. The frequency and duration of monitoring shall be adjusted in accordance with survey results, the nature of construction activities, and results during the monitoring period. A written report of the results of the monitoring shall be prepared and filed with the appropriate Information Center of the California Historical Resources Information System. In the event of a discovery, Cal Poly shall implement item (5), below.
- 3. For project sites requiring intensive investigation, irrespective of subsurface finds, Cal Poly shall retain a qualified archaeologist to conduct a subsurface investigation of the project site, to ascertain whether buried archaeological materials are present and, if so, the extent of the deposit relative to the project's area of effects. If an archaeological deposit is discovered, the archaeologist shall prepare a site record and a written report of the results of investigations and filed with the appropriate Information Center of the California Historical Resources Information System.

- 4. If it is determined that the resource extends into the project's area of effects, the resource shall be evaluated by a qualified archaeologist, who shall determine whether it qualifies as a historical resource or a unique archaeological resource under the criteria of State CEQA Guidelines Section 15064.5. If the resource does not qualify, or if no resource is present within the project's area of effects, this shall be noted in the environmental document and no further mitigation is required unless there is a discovery during construction. In the event of a discovery item (5), below shall be implemented.
- 5. If archaeological material within the project's area of effects is determined to qualify as an historical resource or a unique archaeological resource (as defined by CEQA), Cal Poly Facilities Management and Development shall consult with the qualified archaeologist to consider means of avoiding or reducing ground disturbance within the site boundaries, including minor modifications of building footprint, landscape modification, the placement of protective fill, the establishment of a preservation easement, or other means that shall permit avoidance or substantial preservation in place of the resource. If avoidance or substantial preservation in place is not possible, Cal Poly shall implement Mitigation Measure 3.4-2b. 6) If archaeological material is discovered during construction (whether or not an archaeologist is present), all soil disturbing work within 100 feet of the find shall cease. Cal Poly Facilities Management and Development shall contact a qualified archaeologist to provide and implement a plan for survey, subsurface investigation as needed to define the deposit, and assessment of the remainder of the site within the project area to determine whether the resource is significant and would be affected by the project. Mitigation Measure 3.4-2a (3) and (4) shall be implemented.

# 3.4-2b: Protect Known Unique Archaeological Resources

For an archaeological site that has been determined by a qualified archaeologist to qualify as a unique archaeological resource through the process set forth under Mitigation Measure 3.4-2a, and where it has been determined under Mitigation Measure 3.4-2a that avoidance or preservation in place is not feasible, a qualified archaeologist, in consultation with Cal Poly Facilities Management and Development, and Native American tribes as applicable, shall:

- 1. Prepare a research design and archaeological data recovery plan for the recovery that shall capture those categories of data for which the site is significant and implement the data recovery plan before or during development of the site.
- 2. Perform appropriate technical analyses, prepare a full written report and file it with the appropriate information center, and provide for the permanent curation of recovered materials.
- 3. If, in the opinion of the qualified archaeologist and in light of the data available, the significance of the site is such that data recovery cannot capture the values that qualify the site for inclusion on the CRHR, Cal Poly Facilities Management and Development shall reconsider project plans in light of the high value of the resource, and implement more substantial modifications to the project that would allow the site to be preserved intact, such as project redesign, placement of fill, or project relocation or abandonment. If no such measures are feasible, Cal Poly shall implement Mitigation Measure 3.4-2c.

# 3.4-2c: Document Unique Archaeological Resources

If a significant unique archaeological resource cannot be preserved intact, before the property is damaged or destroyed, Cal Poly Facilities Management and Development shall ensure that the resource is appropriately documented. For an archaeological site, a program of research-directed data recovery shall be conducted and reported, consistent with Mitigation Measure 3.4-2a.

# **BIOLOGICAL RESOURCES**

# 3.5-2h: Conduct Environmental Monitoring

For projects and locations where mitigation measures are required to protect biological resources during construction activities, Cal Poly shall retain an environmental monitor to ensure compliance with the EIR mitigation measures. The monitor shall be responsible for: (1) ensuring that procedures for verifying compliance with environmental mitigations are implemented; (2) establishing lines of communication and reporting methods; (3)

conducting compliance reporting; (4) conducting construction crew training regarding environmentally sensitive areas and/or special-status species; (5) maintaining authority to stop work; and (6) outlining actions to be taken in the event of non-compliance. Monitoring shall be conducted full time during the initial vegetation removal (clear/grub activities), then periodically throughout project construction, or at a frequency and duration as directed by the affected natural resource agencies (e.g., USACE, USFWS, CDFW, and RWQCB).

# 3.5-2u: Conduct Special-Status Bird and Other Bird Nest Avoidance

For any project-specific construction activities under the 2035 Master Plan, the following measures shall be implemented to avoid or minimize loss of active special-status bird nests including tricolored blackbird, grasshopper sparrow, burrowing owl, western yellow-billed cuckoo, white-tailed kite, least Bell's vireo, loggerhead shrike, and purple martin:

- a) To minimize the potential for loss of special-status or other bird nests, vegetation removal activities within potentially suitable nesting habitat shall commence during the nonbreeding season (September 16 January 31), where feasible.
- b) If project construction activities, including ground-disturbing activities, vegetation trimming, or tree removal are scheduled to occur between February 1 and September 15, the following measures shall be implemented:
  - i. For project sites on or within 500 feet of agricultural land, pasture, non-native annual grassland, or riparian habitat as shown in Figure 3.5-1, "Land Cover," and ornamental/landscaping trees in developed habitat, Cal Poly shall retain a qualified biologist to conduct habitat assessment surveys for tricolored blackbird, grasshopper sparrow, burrowing owl, western yellow-billed cuckoo, white-tailed kite, least Bell's vireo, loggerhead shrike, and purple martin. If no suitable habitat is present within 500 feet of the project site, no further action is required.
  - ii. Where suitable habitat is present, surveys shall be conducted by biologists adhering to guidance offered in Western Yellow-billed Cuckoo Natural History Summary and Survey Methodology (Halterman et al. 2015); Least Bell's Vireo Survey Guidelines (USFWS 2001); CDFW Staff Report on Burrowing Owl Mitigation (CDFW 21012) and/or current industry standards. Cal Poly shall initiate consultation with USFWS and/or CDFW as required and shall mitigate for the loss of breeding and foraging habitat as determined by consultation.
  - iii. Two weeks prior to construction, a pre-construction nesting bird survey shall be conducted within suitable habitat identified in Mitigation Measure 3.5-2u(b)(i). If nests of these species are detected, a qualified biologist shall establish no-disturbance buffers around nests. Buffers shall be of sufficient width that breeding is not likely to be disrupted or adversely affected by construction. No-disturbance buffers around active nests shall be a minimum of 0.25 mile wide for white-tailed kite, 500 feet wide for other raptors, and 250 feet wide for other special-status birds, unless a qualified biologist determines based on site-specific conditions that a larger or smaller buffer would be sufficient to avoid impacts on nesting birds. Factors to be considered in determining buffer size shall include the presence of existing buffers provided by vegetation, topography, or existing buildings/structures; nest height; locations of foraging territory; and baseline levels of noise and human activity. Buffers shall be maintained until a qualified biologist has determined that young have fledged and are no longer reliant upon the nest or parental care for survival. Monitoring of the nest by a qualified biologist during and after construction activities shall be required if the activity has potential to adversely affect the nest.
  - iv. For tricolored blackbird, the qualified biologist shall conduct preconstruction surveys within tules, cattails, Himalayan blackberry, and riparian scrub habitat areas. The surveys shall be conducted no more than 14 days before construction commences. If no active nests or tricolored blackbird colonies are found during focused surveys, no further action under this measure shall be required. If active nests are located during the preconstruction surveys, the biologist shall notify CDFW. If necessary, modifications to the project design to avoid removal of occupied habitat while still achieving project objectives shall be evaluated and implemented to the extent feasible. If avoidance is not feasible or conflicts with project objectives, construction shall be prohibited within a minimum of 100 feet of the outer edge of the nesting colony, unless a qualified biologist determines based on site-specific conditions that a larger or smaller buffer would be sufficient, to avoid disturbance until the nest colony is no longer active.

# 3.5-2v: Conduct Environmental Monitoring

During construction of future development within the active nesting season where nesting birds have been found and a no-disturbance buffer is established, implement Mitigation Measure 3.5-2h, described above.

# 3.5-2w: Implement Bat Preconstruction Surveys and Exclusion

Before commencing construction activities with the potential to affect bats, including land surveying with a Global Positioning System (GPS) Total Station and removal of farm structures and trees with hollows or exfoliating bark suitable for bats, a qualified biologist shall conduct surveys for roosting bats 2 weeks prior to start of construction activities. GPS Total Stations used for land surveying emit high frequency noise outside of the human hearing frequency but within the hearing range of bats, which has resulted in colony abandonment. If evidence of bat use is observed, the species and number of bats using the roost shall be determined. Bat detectors may be used to supplement survey efforts. If no evidence of bat roosts is found, then no further study and no additional measures are required. If the roost site can be avoided, a 250-foot-wide no-disturbance buffer shall be implemented unless a qualified biologist determines, based on bat species and site-specific conditions, that a larger or smaller buffer would be adequate to avoid impacts on bat roosts.

If roosts of pallid bat or other bat species are found, and the roost cannot be avoided, bats shall be excluded from the roosting site before the tree or structure is removed. Exclusion efforts shall be restricted during periods of sensitive activity (e.g., during hibernation or while females in maternity colonies are nursing young). Once it is confirmed that bats are not present in the original roost site, the tree or structure may be removed. A detailed program to identify exclusion methods and roost removal procedures shall be developed by a qualified biologist in consultation with CDFW before implementation.

# 3.5-2x: Conduct Environmental Monitoring

If construction of future development would occur where an active bat roost or maternity colony is found and a nodisturbance buffer has been established, conduct environmental monitoring as described in Mitigation Measure 3.5-2h.

# 3.5-3g: Avoid Planting Invasive Plants

Project landscaping shall not utilize any species included on the most recent Cal-IPC Inventory.

# 3.5-3h: Use Clean and Weed-Free Vehicles and Equipment

- a) Cal Poly shall require of its contractor(s) that all vehicles and construction equipment arrive at project areas clean and weed free to avoid inadvertent transport of invasive species. Equipment shall be inspected by the on-site inspector or environmental monitor for mud and other signs that weed seeds or propagules could be present prior to use in project areas in or near sensitive natural communities. If the equipment is not clean, the environmental inspector or monitor shall deny access to the work areas until the equipment is clean.
- b) Vehicles and equipment shall be cleaned using high-pressure water or air in designated weed-cleaning stations after exiting a weed-infested area. Cleaning stations shall be designated by a botanist or noxious weed specialist and located away from aquatic resources, riparian areas, and other sensitive natural communities.

# 3.5-3i: Require Use of Certified Weed-Free Construction Materials

Only certified weed-free construction materials, such as sand, gravel, straw, or fill, shall be used throughout each project site.

# 3.5-3j: Treat Invasive Plant Infestations

Before construction activities begin, Cal Poly shall treat invasive plant infestations in the construction area, and within 50 feet of the construction activity area. Any new invasive plant infestations discovered during construction shall be documented, reported to Cal Poly, and treated where needed. After construction is complete, Cal Poly or its contractors shall monitor all construction disturbance areas for new invasive plant invasions and expansion of existing weed populations and treat invasive plan infestations where needed. Post-construction monitoring for invasive plant infestations would be conducted annually for 3 years within sensitive natural communities.

# GEOLOGY AND SOILS

# 3.7-3: Perform Site-Specific Geotechnical Investigations

For any areas within the campus where development is proposed in an area designated as having a high potential for landslide hazards, have substantial erosion potential, or be located on a geologic unit that is unstable or within an area known to have expansive soils, a site-specific geotechnical investigation shall be performed. Based on the findings of the geotechnical investigation for each future development or redevelopment projects under the 2035 Master Plan, any appropriate stabilization and site design recommendations, or low impact development features determined necessary to support proposed development shall be incorporated in the project design and implemented as part of project construction. Examples of stabilization and erosion control recommendations may include, but are not limited to:

- installation of earthen buttress(es);
- excavation of landslide mass/material;
- slope stabilization through excavation into benches and/or keyways and other methods;
- deep soil mixing;
- installation of retaining walls;
- ▶ use of tie-back anchors, micropiles, or shear pins; or
- ► a combination of any of these methods.

Before final plan approval, Cal Poly shall incorporate into the project design and implement all recommendations identified in the site-specific geotechnical investigation, including all recommendations included in the final geotechnical report prepared for the project. All recommendations shall be shown on final plans and/or included as project specifications.

# 3.7-7: Treatment of Paleontological Resources

If any paleontological resources are encountered during ground-disturbing activities, the construction contractor shall ensure that activities in the immediate area of the find are halted and Cal Poly informed. Cal Poly shall retain a qualified paleontologist to evaluate the discovery and recommend appropriate treatment options pursuant to guidelines developed by the Society of Vertebrate Paleontology, including development and implementation of a paleontological resource impact mitigation program for treatment of the resource, if applicable.

# GREENHOUSE GAS EMISSIONS

### 3.8-1: Implement On-Site GHG Reduction

Measures Cal Poly shall implement the following GHG reduction measures:

- Design all new and renovated buildings to achieve a 30-percent or greater reduction in energy use compared to a standard 2019 California Energy Code-compliant building or other best practices as defined by CSU Sustainability Policy. Reductions in energy shall be achieved through energy efficiency measures consistent with Tier 2 of the California Green Building Energy Code Section A5.203.1.2.2.
- Design all new and renovated buildings to include Cool Roofs in accordance with the requirements set forth in Tier 2 of the 2019 California Green Building Energy Code, Sections A5.106.11.2.
- Install rooftop solar photovoltaics on all new and renovated buildings, including parking structures, where specific site parameters and constraints allow for adequate rooftop space. The amount of megawatt-hours that would be installed to offset electricity consumption would be based on the feasibility at each building site.
- ► Ensure that all new and renovated buildings comply with requirements for water efficiency and conservation as described in the 2019 California Green Building Standards Code, Division 5.3.

- Ensure that all new parking structures include preferential parking spaces to vehicles with more than one occupant and ZEVs. The number of dedicated spaces will be no less than 5 percent of the total parking spaces. These dedicated spaces shall be in preferential locations, such as near the entrance to the parking structure. ZEV spaces shall also include campus-standard electric vehicle charging stations, with electrical infrastructure capacity to expand charging stations by a factor of four as the number of electric vehicle drivers grows. These spaces shall be clearly marked with signs and pavement markings. This measure shall not be implemented in a way that prevents compliance with requirements in the California Vehicle Code regarding parking spaces for disabled persons or disabled veterans.
- Include multiple electrical receptacles on the exterior of all new and renovated buildings and accessible for purposes of charging or powering electric landscaping equipment and providing an alternative to using fossil fuel-powered generators. The electrical receptacles shall have an electric potential of 120 volts. There should be a minimum of one electrical receptacle on each building and one receptacle every 100 linear feet around the perimeter of the building.
- Ensure that all appliances and fixtures installed in project buildings are EnergyStar®-certified if an EnergyStar®-certified model of the appliance is available. Types of EnergyStar®-certified appliances include boilers, ceiling fans, central and room air conditioners, clothes washers, compact fluorescent light bulbs, computer monitors, copiers, consumer electronics, dehumidifiers, dishwashers, external power adapters, furnaces, geothermal heat pumps, programmable thermostats, refrigerators and freezers, room air cleaners, transformers, televisions, vending machines, ventilating fans, and windows (EPA 2018). If EPA's EnergyStar® program is discontinued and not replaced with a comparable certification program before appliances and fixtures are selected, then similar measures which exceed the 2019 California Green Building Standards Code may be used.
- Ensure that all space and water heating is solar- or electric-powered.
- Install high-efficacy lighting (e.g., light emitting diodes) in all streetlights, security lighting, and all other exterior lighting applications.
- Accomplish a waste diversion rate of 90 percent by and strive for 100 percent by 2040.
- > Plant water-efficient and drought tolerant landscapes at all project buildings.

In addition to the quantifiable onsite measures presented above, the following additional measures would reduce GHG emissions, although the extent to which they would reduce GHG emissions is not quantifiable. Nonetheless, Cal Poly shall implement the following measures as part of implementation of the 2035 Master Plan and the Cal Poly Climate Action Plan to the extent feasible.

- At the time of contract renegotiation, work with current car share companies (e.g., ZIP car) to increase the use of fully electric vehicles or consider partnerships with other similar services that do use electric vehicles.
- Where appropriate site conditions exist, install solar photovoltaics on available land throughout the Cal Poly campus to offset the use of nonrenewable energy for existing and future facilities and buildings.
- Cal Poly shall work with San Luis Obispo County, the City of San Luis Obispo, TriCounty Regional Energy Network (3C-REN), and other local agencies to determine if Cal Poly can fund and take GHG reduction credit for energy efficiency retrofits of local existing housing stock, commercial spaces, and other land uses.
- ► Accelerate the expansion of Cal Poly's fleet vehicles to electric.
- Accelerate the expansion of Level 2 EV chargers on campus to meet the anticipated demand at Cal Poly.
- ▶ Implement energy efficiency retrofits for existing buildings on campus that will remain.
- Work with SLO Regional Rideshare to refine Cal Poly's use of the iRideshare trip reporting/incentive platform to help VMT and emission reduction goals.

- To help commute incentives more effectively change commute behavior to benefit VMT, emissions, and the modal hierarchy:
  - Expand faculty and staff daily benefits for using alternative transportation modes to an effective amount.
  - Consider reducing the frequency between parking permit purchasing (e.g. weekly, monthly)
  - Consider increasing faculty and staff parking permit costs over time.

# HYDROLOGY AND WATER QUALITY

### 3.9-3: Prepare Drainage Plan and Supportive Hydrologic Analysis

Before the commencement of construction activities associated with new development that will modify existing drainage and/or require the construction of new drainage infrastructure to collect and control storm water runoff, Cal Poly shall prepare a drainage plan and supportive hydrologic analysis demonstrating compliance with the following, or equally effective similar measures, to maximize groundwater recharge and maintain similar drainage patterns and flow rates:

- a) Off-site runoff shall not exceed existing flow rates during storm events.
- b) If required to maintain the current flow rate, appropriate methods/design features (e.g., detention/retention basins, infiltration systems, or bioswales) shall be installed to reduce local increases in runoff, particularly on frequent runoff events (up to 10-year frequency) and to maximize groundwater recharge.
- c) If proposed, drainage discharge points shall include erosion protection and be designed such that flow hydraulics exiting the site mimics the natural condition as much as possible.
- d) Drainage from impervious surfaces (e.g., roads, driveways, buildings) shall be directed to a common drainage basin.
- e) Where feasible, grading and earth contouring shall be done in a way to direct surface runoff towards the above-referenced drainage improvements (and/or closed depressions).

# 3.9-4a: Prepare a Drainage Plan and Supportive Hydrologic Analysis

Implement Mitigation Measure 3.9-3, described above.

### 3.9-4b: Implement Post-Development Storm Water Best Management Practices and Low-Impact Development

During the design review phase of each future development project within the Master Plan Area, Facilities Management and Development will verify that the storm water BMPs and LID technologies were evaluated for each project within the 2035 Master Plan and all appropriate BMPs are incorporated into the specific project. Additionally, consistent with MS4 requirements, Facilities Management and Development will also verify that post-development runoff from the project site will approximate pre-development runoff volumes. If post-development runoff does not approximate pre-development runoff, additional BMPs shall be required in order to ensure that storm drain system capacity is not exceeded and that the drainage pattern of each project site is not significantly altered in such a way that it would result in erosion, siltation, or flooding.

# NOISE

# 3.10-1: Implement Construction-Noise Reduction Measures (as amended)

For all construction activities related to new/renovated structures, Cal Poly shall implement or incorporate the following noise reduction measures into construction specifications for contractor(s) implementation during project construction:

- All construction equipment shall be properly maintained and equipped with noise-reduction intake and exhaust mufflers and engine shrouds, in accordance with manufacturer recommendations. Equipment engine shrouds shall be closed during equipment operation.
- All construction equipment and equipment staging areas shall be located as far as feasible from nearby noisesensitive land uses, and/or located to the extent feasible such that existing or constructed noise attenuating features (e.g., temporary noise wall or blankets) block line-of-sight between affected noise-sensitive land uses and construction staging areas.
- Individual operations and techniques shall be replaced with quieter procedures (e.g., using welding instead of riveting, mixing concrete off-site instead of on-site, using electric powered equipment instead of pneumatic or internal combustion powered equipment) where feasible and consistent with building codes and other applicable laws and regulations.
- Stationary noise sources such as generators or pumps shall be located as far away from noise-sensitive uses as feasible.
- ► No less than 1 week prior to the start of construction activities at a particular location, notification shall be provided to nearby off-campus, noise-sensitive land uses (e.g., residential uses) that are located within 350 feet of the construction site (i.e., based on the construction noise modeling, distance at which noise-sensitive receptors would experience noise levels exceeding acceptable daytime construction-noise levels).
- ► When construction would occur within 350 feet of on-campus housing or other on-campus or off-campus noisesensitive uses and may result in temporary noise levels in excess of 75 L<sub>max</sub> at the exterior of the adjacent noisesensitive structure, temporary noise barriers (e.g., noise-insulating blankets or temporary plywood structures) shall be erected, if deemed to be feasible and effective, between the noise source and sensitive receptor such that construction-related noise levels are reduced to 75 L<sub>max</sub> or less at the receptor.]
- ► Loud construction activity (e.g., jackhammering, concrete sawing, asphalt removal, and large-scale grading operations) within 350 feet of adjacent primary school facilities, shall not occur during state standardized testing time periods for the surrounding school districts.
- ► When construction requires material hauling, a haul route plan shall be prepared for construction of each facility and/or improvement for review and approval by the Cal Poly that designates haul routes as far as feasible from sensitive receptors.
- ► The contractor shall designate a disturbance coordinator and post that person's telephone number conspicuously around the construction site and provide to nearby residences. The disturbance coordinator shall receive all public complaints and be responsible for determining the cause of the complaint and implementing any feasible measures to alleviate the problem.
- ► Construction activities (excluding activities that would result in a safety concern to the public or construction workers) shall be limited to between the hours of 7:00 a.m. and 7:00 p.m., Monday through Saturday, where feasible. Although potential impacts were determined to be significant and unavoidable, for any construction activity that must extend beyond the daytime hours of 7:00 a.m. and 7:00 p.m. Monday through Saturday, occur on Sunday, or legal holidays and occur within 2,000 feet of a residential building, Cal Poly shall comply, to the extent feasible, with the City of San Luis Obispo exterior noise level standard of 60 dBA L<sub>max</sub> for temporary construction noise at off-campus residences. Typical residential structures with windows closed achieve a 25-30 dBA exterior-to-interior noise reduction (Caltrans 2002). Thus, using the lower end of this range, an exterior noise level of 60 dBA L<sub>max</sub> would result in interior noise levels of about 35 dBA L<sub>max</sub>, which would not result in a substantially increased risk for sleep disturbance. If exterior noise levels of 60 dBA L<sub>max</sub> are infeasible due to the type of construction activity and proximity to residential structures, achieving interior noise levels of 45 dBA L<sub>eq</sub> or less, consistent with City standards, would prevent nearby residents from being disturbed. One or more of the following or equivalent measures shall be considered and implemented to the extent feasible and effective:

- Use noise-reducing enclosures and techniques around stationary noise-generating equipment (e.g., concrete mixers, generators, compressors).
- Install temporary noise curtains as close as possible to the boundary of the construction site within the direct line of sight path of the nearby sensitive receptor(s) that consist of durable, flexible composite material featuring a noise barrier layer bounded to sound-absorptive material on one side.
- Retain a qualified noise specialist to develop a noise monitoring plan and conduct noise monitoring to
  ensure that effective noise reduction measures are implemented to achieve exterior noise levels of 60 dBA
  L<sub>max</sub> or less at off-campus residences for construction activity occurring during these noise-sensitive hours to
  the maximum extent feasible.

# 3.10-3c: Implement Noise Reduction Measures to Reduce Long-Term Noise Impacts of Building Mechanical Equipment

To minimize noise levels generated by building mechanical equipment, the following measures shall be implemented:

Building air conditioning units for proposed structures shall be located on building rooftops or shielded from direct line-of-sight of adjacent noise-sensitive land uses. Building parapets shall be constructed, when necessary, to shield nearby land uses from direct line-of-site of air conditioning units.

During project design of individual projects proposed as part of the 2035 Master Plan, Cal Poly shall review and ensure that external building mechanical equipment (e.g., HVAC systems) incorporate noise-reduction features sufficient to reduce average-hourly exterior operational noise levels at nearby noise-sensitive land uses to 50 L<sub>eq</sub> and 70 dba L<sub>max</sub>, or less during the daytime (i.e., 7:00 a.m. to 10:00 p.m.) and 45 L<sub>eq</sub> and 60 dBA L<sub>max</sub>, or less during the nighttime (i.e., 10:00 p.m. to 7:00 a.m.), within outdoor activity areas. Noise-reduction measures to be incorporated may include, but are not limited to, the selection of alternative or lower noise-generating equipment, relocation of equipment, and use of equipment enclosures.

# 3.10-4a: Implement Measures to Reduce Ground Vibration

For any future construction activity that would involve pile driving and be located within 300 feet of an existing sensitive land use or occupied building, the following measures shall be implemented:

- ► To the extent feasible, earthmoving and ground-impacting operations shall be phased so as not to occur simultaneously in areas close to sensitive receptors (i.e., within 300 feet). The total vibration level produced could be significantly less when each vibration source is operated at separate times.
- ► Where there is flexibility in the location of use of heavy-duty construction equipment, or impact equipment, the equipment shall be operated as far away from vibration-sensitive sites as reasonably feasible.
- ▶ 3.10-4b: Develop and Implement a Vibration Control Plan

To assess and, when needed, reduce vibration and noise impacts from construction activities, the following measures shall be implemented:

- ► A vibration control plan shall be developed prior to initiating any pile-driving activities. Applicable elements of the plan shall be implemented before, during, and after pile-driving activity. The plan will include measures sufficient to reduce vibration at sensitive receptors to levels below applicable thresholds. Items that will be addressed in the plan include, but are not limited to, the following:
  - Identification of the maximum allowable vibration levels at nearby buildings may consider Caltrans's recommended standards with respect to the prevention of architectural building damage of 0.25 in/sec PPV for historic and some old buildings and for buildings that are occupied at the time of pile driving, FTA's maximum-acceptable-vibration standard with respect to human response, 80 VdB. However, based on site-specific parameters (e.g., building age, structural integrity), and construction specifics (e.g., time of day when vibration activities occur, pile frequency), these standards may be adjusted, as long as sensitive receptors and structures are protected.

- Pre-construction surveys shall be conducted to identify any pre-existing structural damage to buildings that may be affected by project-generated vibration.
- Identification of minimum setback requirements for different types of ground-vibration-producing activities (e.g., pile driving) for the purpose of preventing damage to nearby structures and preventing adverse effects on people. Factors to be considered include the nature of the vibration-producing activity, local soil conditions, and the fragility/resiliency of the nearby structures. Initial setback requirements can be reduced if a project- and site-specific analysis is conducted by a qualified geotechnical engineer or ground vibration specialist that indicates that no structural damage to buildings or structures would occur.
- Vibration levels from pile driving shall be monitored and documented at the nearest sensitive land use to
  document that applicable thresholds are not exceeded. Recorded data shall be submitted on a twice-weekly
  basis to Cal Poly. If it is found at any time that thresholds are exceeded, pile driving shall cease in that
  location, and methods shall be implemented to reduce vibration to below applicable thresholds, or an
  alternative pile installation method shall be used at that location.

# Appendix B

# Air Quality Modeling Results

# **Student Success Center Detailed Report**

# Table of Contents

- 1. Basic Project Information
  - 1.1. Basic Project Information
  - 1.2. Land Use Types
  - 1.3. User-Selected Emission Reduction Measures by Emissions Sector
- 2. Emissions Summary
  - 2.1. Construction Emissions Compared Against Thresholds
  - 2.2. Construction Emissions by Year, Unmitigated
  - 2.3. Construction Emissions by Year, Mitigated
  - 2.4. Operations Emissions Compared Against Thresholds
  - 2.5. Operations Emissions by Sector, Unmitigated
  - 2.6. Operations Emissions by Sector, Mitigated
- 3. Construction Emissions Details
  - 3.1. Demolition (2025) Unmitigated
  - 3.2. Demolition (2025) Mitigated
  - 3.3. Site Preparation (2025) Unmitigated

- 3.4. Site Preparation (2025) Mitigated
- 3.5. Grading (2025) Unmitigated
- 3.6. Grading (2025) Mitigated
- 3.7. Building Construction (2025) Unmitigated
- 3.8. Building Construction (2025) Mitigated
- 3.9. Building Construction (2026) Unmitigated
- 3.10. Building Construction (2026) Mitigated
- 3.11. Paving (2026) Unmitigated
- 3.12. Paving (2026) Mitigated
- 3.13. Architectural Coating (2026) Unmitigated
- 3.14. Architectural Coating (2026) Mitigated
- 3.15. Architectural Coating (2027) Unmitigated
- 3.16. Architectural Coating (2027) Mitigated
- 4. Operations Emissions Details
  - 4.1. Mobile Emissions by Land Use
    - 4.1.1. Unmitigated
    - 4.1.2. Mitigated
  - 4.2. Energy

- 4.2.1. Electricity Emissions By Land Use Unmitigated
- 4.2.2. Electricity Emissions By Land Use Mitigated
- 4.2.3. Natural Gas Emissions By Land Use Unmitigated
- 4.2.4. Natural Gas Emissions By Land Use Mitigated
- 4.3. Area Emissions by Source
  - 4.3.1. Unmitigated
  - 4.3.2. Mitigated
- 4.4. Water Emissions by Land Use
  - 4.4.1. Unmitigated
  - 4.4.2. Mitigated
- 4.5. Waste Emissions by Land Use
  - 4.5.1. Unmitigated
  - 4.5.2. Mitigated
- 4.6. Refrigerant Emissions by Land Use
  - 4.6.1. Unmitigated
  - 4.6.2. Mitigated
- 4.7. Offroad Emissions By Equipment Type
  - 4.7.1. Unmitigated

#### 4.7.2. Mitigated

- 4.8. Stationary Emissions By Equipment Type
  - 4.8.1. Unmitigated
  - 4.8.2. Mitigated
- 4.9. User Defined Emissions By Equipment Type
  - 4.9.1. Unmitigated
  - 4.9.2. Mitigated
- 4.10. Soil Carbon Accumulation By Vegetation Type
  - 4.10.1. Soil Carbon Accumulation By Vegetation Type Unmitigated
  - 4.10.2. Above and Belowground Carbon Accumulation by Land Use Type Unmitigated
  - 4.10.3. Avoided and Sequestered Emissions by Species Unmitigated
  - 4.10.4. Soil Carbon Accumulation By Vegetation Type Mitigated
  - 4.10.5. Above and Belowground Carbon Accumulation by Land Use Type Mitigated
  - 4.10.6. Avoided and Sequestered Emissions by Species Mitigated
- 5. Activity Data
  - 5.1. Construction Schedule
  - 5.2. Off-Road Equipment
    - 5.2.1. Unmitigated

5.2.2. Mitigated

- 5.3. Construction Vehicles
  - 5.3.1. Unmitigated

5.3.2. Mitigated

- 5.4. Vehicles
  - 5.4.1. Construction Vehicle Control Strategies
- 5.5. Architectural Coatings
- 5.6. Dust Mitigation
  - 5.6.1. Construction Earthmoving Activities
  - 5.6.2. Construction Earthmoving Control Strategies
- 5.7. Construction Paving
- 5.8. Construction Electricity Consumption and Emissions Factors
- 5.9. Operational Mobile Sources
  - 5.9.1. Unmitigated
  - 5.9.2. Mitigated
- 5.10. Operational Area Sources
  - 5.10.1. Hearths
    - 5.10.1.1. Unmitigated

### 5.10.1.2. Mitigated

- 5.10.2. Architectural Coatings
- 5.10.3. Landscape Equipment
- 5.10.4. Landscape Equipment Mitigated
- 5.11. Operational Energy Consumption
  - 5.11.1. Unmitigated
  - 5.11.2. Mitigated
- 5.12. Operational Water and Wastewater Consumption
  - 5.12.1. Unmitigated
  - 5.12.2. Mitigated
- 5.13. Operational Waste Generation
  - 5.13.1. Unmitigated
  - 5.13.2. Mitigated
- 5.14. Operational Refrigeration and Air Conditioning Equipment
  - 5.14.1. Unmitigated
  - 5.14.2. Mitigated
- 5.15. Operational Off-Road Equipment
  - 5.15.1. Unmitigated

5.15.2. Mitigated

### 5.16. Stationary Sources

5.16.1. Emergency Generators and Fire Pumps

5.16.2. Process Boilers

5.17. User Defined

### 5.18. Vegetation

5.18.1. Land Use Change

5.18.1.1. Unmitigated

5.18.1.2. Mitigated

5.18.1. Biomass Cover Type

5.18.1.1. Unmitigated

5.18.1.2. Mitigated

### 5.18.2. Sequestration

5.18.2.1. Unmitigated

5.18.2.2. Mitigated

6. Climate Risk Detailed Report

# 6.1. Climate Risk Summary

6.2. Initial Climate Risk Scores

- 6.3. Adjusted Climate Risk Scores
- 6.4. Climate Risk Reduction Measures
- 7. Health and Equity Details
  - 7.1. CalEnviroScreen 4.0 Scores
  - 7.2. Healthy Places Index Scores
  - 7.3. Overall Health & Equity Scores
  - 7.4. Health & Equity Measures
  - 7.5. Evaluation Scorecard
  - 7.6. Health & Equity Custom Measures
- 8. User Changes to Default Data

# 1. Basic Project Information

# 1.1. Basic Project Information

Data Field	Value
Project Name	Student Success Center
Construction Start Date	9/1/2025
Operational Year	2027
Lead Agency	California Polytechnic State University
Land Use Scale	Project/site
Analysis Level for Defaults	County
Windspeed (m/s)	3.20
Precipitation (days)	32.4
Location	35.303200963844276, -120.65970314753952
County	San Luis Obispo
City	Unincorporated
Air District	San Luis Obispo County APCD
Air Basin	South Central Coast
TAZ	3331
EDFZ	6
Electric Utility	Pacific Gas & Electric Company
Gas Utility	Southern California Gas
App Version	2022.1.1.29

# 1.2. Land Use Types

Land Use Subtype	Size	Unit	Lot Acreage	Building Area (sq ft)	Landscape Area (sq ft)	Special Landscape Area (sq ft)	Population	Description
User Defined Educational	36.0	User Defined Unit	1.30	360,000	38,000	—	—	—

# 1.3. User-Selected Emission Reduction Measures by Emissions Sector

Sector	#	Measure Title
Construction	C-2*	Limit Heavy-Duty Diesel Vehicle Idling
Construction	C-10-A	Water Exposed Surfaces
Construction	C-11	Limit Vehicle Speeds on Unpaved Roads
Construction	C-12	Sweep Paved Roads
Construction	C-13	Use Low-VOC Paints for Construction
Energy	E-15	Require All-Electric Development

\* Qualitative or supporting measure. Emission reductions not included in the mitigated emissions results.

# 2. Emissions Summary

# 2.1. Construction Emissions Compared Against Thresholds

Un/Mit.	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	-	-	-	-	—		_	_	_	_	—	_	_
Unmit.	1.65	11.7	15.3	0.48	1.21	1.52	0.45	0.30	0.58	—	4,007	4,007	0.15	0.24	6.81	4,090
Mit.	1.65	11.7	15.3	0.48	1.21	1.52	0.45	0.30	0.58	—	4,007	4,007	0.15	0.24	6.81	4,090
% Reduced	-	-	-	—	—	—	—	-	—	—	_	—	-	-	-	-
Daily, Winter (Max)	—	—	—	_	_	_	_	—		_	_	_	—		—	-
Unmit.	209	24.2	18.1	0.77	8.94	9.71	0.68	3.93	4.61	_	9,540	9,540	0.47	1.15	0.36	9,895
Mit.	42.0	24.2	18.1	0.77	4.58	5.35	0.68	1.84	2.52	_	9,540	9,540	0.47	1.15	0.36	9,895
% Reduced	80%	_	_	_	49%	45%	_	53%	45%	_	_	_	_	_	_	_

Average Daily (Max)																
Unmit.	13.7	6.74	9.49	0.20	0.72	0.91	0.18	0.23	0.36	—	2,435	2,435	0.09	0.15	1.77	2,482
Mit.	3.55	6.74	9.49	0.20	0.72	0.91	0.18	0.18	0.36	—	2,435	2,435	0.09	0.15	1.77	2,482
% Reduced	74%							23%		—		—		—		
Annual (Max)		—	—	—	—			—	—	—	—	—	—	—		
Unmit.	2.49	1.23	1.73	0.04	0.13	0.17	0.03	0.04	0.07	—	403	403	0.02	0.02	0.29	411
Mit.	0.65	1.23	1.73	0.04	0.13	0.17	0.03	0.03	0.07	—	403	403	0.02	0.02	0.29	411
% Reduced	74%	—	—	—	—			23%	—	—		—				

# 2.2. Construction Emissions by Year, Unmitigated

Year	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily - Summer (Max)	-	-	-	-	-	_	-	—	—	-	_	—	_	—	—	—
2025	1.28	11.7	11.5	0.48	0.04	0.53	0.45	0.01	0.46		1,958	1,958	0.08	0.02	0.19	1,966
2026	1.65	10.8	15.3	0.31	1.21	1.52	0.29	0.30	0.58	_	4,007	4,007	0.15	0.24	6.81	4,090
Daily - Winter (Max)	—	_	—	-	-	_	_	—		_	_		_	—		_
2025	1.72	24.2	18.1	0.77	8.94	9.71	0.68	3.93	4.61	_	9,540	9,540	0.47	1.15	0.36	9,895
2026	209	10.9	15.2	0.31	1.21	1.52	0.29	0.30	0.58	_	3,970	3,970	0.15	0.24	0.18	4,047
2027	209	0.90	1.97	0.02	0.17	0.19	0.02	0.04	0.06	_	304	304	0.01	0.01	0.02	307
Average Daily	-	-	—	_	_	—	—	—	_	_	—	—	—	—	—	-
2025	0.38	3.28	3.52	0.11	0.58	0.69	0.10	0.23	0.33	_	1,028	1,028	0.04	0.08	0.63	1,053
2026	13.7	6.74	9.49	0.20	0.72	0.91	0.18	0.18	0.36	_	2,435	2,435	0.09	0.15	1.77	2,482

2027	10.2	0.04	0.10	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	—	14.9	14.9	< 0.005	< 0.005	0.01	15.1
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
2025	0.07	0.60	0.64	0.02	0.11	0.13	0.02	0.04	0.06	—	170	170	0.01	0.01	0.10	174
2026	2.49	1.23	1.73	0.04	0.13	0.17	0.03	0.03	0.07	—	403	403	0.02	0.02	0.29	411
2027	1.86	0.01	0.02	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	—	2.47	2.47	< 0.005	< 0.005	< 0.005	2.50

# 2.3. Construction Emissions by Year, Mitigated

Year	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily - Summer (Max)	-	—	—	—	-	-	-	—	-	-	-	-	-	-	-	—
2025	1.28	11.7	11.5	0.48	0.04	0.53	0.45	0.01	0.46	—	1,958	1,958	0.08	0.02	0.19	1,966
2026	1.65	10.8	15.3	0.31	1.21	1.52	0.29	0.30	0.58	—	4,007	4,007	0.15	0.24	6.81	4,090
Daily - Winter (Max)	_	_	_	_	_	_	_	_	_	_	_	_	_	_	-	_
2025	1.72	24.2	18.1	0.77	4.58	5.35	0.68	1.84	2.52	—	9,540	9,540	0.47	1.15	0.36	9,895
2026	42.0	10.9	15.2	0.31	1.21	1.52	0.29	0.30	0.58	—	3,970	3,970	0.15	0.24	0.18	4,047
2027	42.0	0.90	1.97	0.02	0.17	0.19	0.02	0.04	0.06	—	304	304	0.01	0.01	0.02	307
Average Daily	-	_	_	-	-	-	-	-	-	-	-	_	_	-	-	_
2025	0.38	3.28	3.52	0.11	0.36	0.47	0.10	0.12	0.22	_	1,028	1,028	0.04	0.08	0.63	1,053
2026	3.55	6.74	9.49	0.20	0.72	0.91	0.18	0.18	0.36	_	2,435	2,435	0.09	0.15	1.77	2,482
2027	2.05	0.04	0.10	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	14.9	14.9	< 0.005	< 0.005	0.01	15.1
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
2025	0.07	0.60	0.64	0.02	0.07	0.09	0.02	0.02	0.04	_	170	170	0.01	0.01	0.10	174
2026	0.65	1.23	1.73	0.04	0.13	0.17	0.03	0.03	0.07		403	403	0.02	0.02	0.29	411
2027	0.37	0.01	0.02	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	2.47	2.47	< 0.005	< 0.005	< 0.005	2.50

# 2.4. Operations Emissions Compared Against Thresholds

Criteria Pollutants	(lb/day for	daily, ton/yr for	annual) and	GHGs (lb/day fo	r daily, MT/yr for annua	al)
---------------------	-------------	-------------------	-------------	-----------------	--------------------------	-----

Un/Mit.	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	-	_	-	_	-	-	_	_	-	_	-	-	-	-	-
Unmit.	12.8	0.41	17.7	0.03	0.48	0.51	0.03	0.12	0.15	0.00	818	818	0.05	0.03	1.98	830
Mit.	12.8	0.41	17.7	0.03	0.48	0.51	0.03	0.12	0.15	0.00	818	818	0.05	0.03	1.98	830
% Reduced	—	—	—	—	—	—	—	-	—	—	—	—	_	_	—	_
Daily, Winter (Max)	_	_	—	_	_	_	_	—	_	_	—	_	_	_	_	_
Unmit.	10.2	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	0.00	737	737	0.05	0.03	0.05	747
Mit.	10.2	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	0.00	737	737	0.05	0.03	0.05	747
% Reduced	—	—	—	—		—	—	—	—	—	—	—	—	—	—	—
Average Daily (Max)	_	-	-	-	_	-	-	-	_	_	-	-	-	-	_	-
Unmit.	12.5	0.38	15.9	0.03	0.40	0.43	0.02	0.10	0.13	0.00	722	722	0.05	0.03	0.73	731
Mit.	12.5	0.38	15.9	0.03	0.40	0.43	0.02	0.10	0.13	0.00	722	722	0.05	0.03	0.73	731
% Reduced	—	_	—	_	_	—	—	—	-	_	—	_	—	_	_	_
Annual (Max)	—	-	-	-	-	_	_	-	-	-	—	-	-	-	-	-
Unmit.	2.28	0.07	2.89	0.01	0.07	0.08	< 0.005	0.02	0.02	0.00	119	119	0.01	< 0.005	0.12	121
Mit.	2.28	0.07	2.89	0.01	0.07	0.08	< 0.005	0.02	0.02	0.00	119	119	0.01	< 0.005	0.12	121
% Reduced	—	-	—	_	_	_	_	-	_	_	_	_	_	_	_	_

# 2.5. Operations Emissions by Sector, Unmitigated

Sector	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)		-		-	-	-	—		—	-	-	-	-		-	-
Mobile	0.22	0.28	2.07	0.01	0.48	0.48	< 0.005	0.12	0.13	—	550	550	0.02	0.02	1.98	559
Area	12.6	0.13	15.7	0.03	—	0.03	0.02	—	0.02	—	64.4	64.4	< 0.005	< 0.005	—	64.6
Energy	0.00	0.00	0.00	0.00	_	0.00	0.00	—	0.00	_	203	203	0.03	< 0.005	—	205
Water	—	—	—	—	_	—	_	—	—	0.00	1.11	1.11	< 0.005	< 0.005	_	1.13
Waste	—	—	—	—	—	—	—	—	—	0.00	0.00	0.00	0.00	0.00	—	0.00
Total	12.8	0.41	17.7	0.03	0.48	0.51	0.03	0.12	0.15	0.00	818	818	0.05	0.03	1.98	830
Daily, Winter (Max)	—	—	—	—	—	—	—	_	—	—	—	—	—	_	—	—
Mobile	0.22	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	—	533	533	0.02	0.02	0.05	541
Area	9.99	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Energy	0.00	0.00	0.00	0.00	—	0.00	0.00	—	0.00	—	203	203	0.03	< 0.005	—	205
Water	—	—	—	—	—	—	—	—	—	0.00	1.11	1.11	< 0.005	< 0.005	—	1.13
Waste	—	—	—	—	—	—	—	—	—	0.00	0.00	0.00	0.00	0.00	—	0.00
Total	10.2	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	0.00	737	737	0.05	0.03	0.05	747
Average Daily	—	—	—	—	—	—	—		—	—	—	—	—	—	—	—
Mobile	0.18	0.26	1.71	< 0.005	0.40	0.41	< 0.005	0.10	0.11	—	459	459	0.02	0.02	0.73	467
Area	12.3	0.12	14.2	0.03	—	0.03	0.02	—	0.02	—	58.2	58.2	< 0.005	< 0.005	—	58.4
Energy	0.00	0.00	0.00	0.00	—	0.00	0.00	—	0.00	—	203	203	0.03	< 0.005	—	205
Water	—	—	—	—	—	—	—	—	—	0.00	1.11	1.11	< 0.005	< 0.005	—	1.13
Waste	_	—	—	_	_	_	—	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	12.5	0.38	15.9	0.03	0.40	0.43	0.02	0.10	0.13	0.00	722	722	0.05	0.03	0.73	731
Annual	_	_	_	_	_	_	_	—	_	_	_	_	_	_	_	_

Mobile	0.03	0.05	0.31	< 0.005	0.07	0.07	< 0.005	0.02	0.02	_	76.0	76.0	< 0.005	< 0.005	0.12	77.3
Area	2.25	0.02	2.58	< 0.005	—	< 0.005	< 0.005	—	< 0.005	—	9.64	9.64	< 0.005	< 0.005	—	9.67
Energy	0.00	0.00	0.00	0.00	—	0.00	0.00	—	0.00	—	33.6	33.6	0.01	< 0.005	—	33.9
Water	—	—	—	—	—	—	—	—	—	0.00	0.18	0.18	< 0.005	< 0.005	—	0.19
Waste	—	—	—	—	—	—	—	—	—	0.00	0.00	0.00	0.00	0.00	—	0.00
Total	2.28	0.07	2.89	0.01	0.07	0.08	< 0.005	0.02	0.02	0.00	119	119	0.01	< 0.005	0.12	121

# 2.6. Operations Emissions by Sector, Mitigated

Sector	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	—	—	-	—	_	_	-	-	—	—	—	-	-	-	-
Mobile	0.22	0.28	2.07	0.01	0.48	0.48	< 0.005	0.12	0.13	—	550	550	0.02	0.02	1.98	559
Area	12.6	0.13	15.7	0.03	—	0.03	0.02	—	0.02	—	64.4	64.4	< 0.005	< 0.005	—	64.6
Energy	0.00	0.00	0.00	0.00	_	0.00	0.00	—	0.00	—	203	203	0.03	< 0.005	—	205
Water	_	-	-	_	_	-	-	_	_	0.00	1.11	1.11	< 0.005	< 0.005	_	1.13
Waste	_	_	_	_	_	-	-	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	12.8	0.41	17.7	0.03	0.48	0.51	0.03	0.12	0.15	0.00	818	818	0.05	0.03	1.98	830
Daily, Winter (Max)	-	_	_	-	_	_	_	_	_	-	_	-	_	-	-	-
Mobile	0.22	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	_	533	533	0.02	0.02	0.05	541
Area	9.99	_	_	_	_	-	-	_	_	_	_	_	_	_	_	_
Energy	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	203	203	0.03	< 0.005	_	205
Water	_	_	_	_	_	-	-	_	_	0.00	1.11	1.11	< 0.005	< 0.005	_	1.13
Waste	_	_	_	_	_	-	-	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	10.2	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	0.00	737	737	0.05	0.03	0.05	747
Average Daily	-	_	_	_	-	_	_	_	_	_	-	_	-	_	-	_

Mobile	0.18	0.26	1.71	< 0.005	0.40	0.41	< 0.005	0.10	0.11	_	459	459	0.02	0.02	0.73	467
Area	12.3	0.12	14.2	0.03	_	0.03	0.02	—	0.02	-	58.2	58.2	< 0.005	< 0.005	—	58.4
Energy	0.00	0.00	0.00	0.00	_	0.00	0.00	—	0.00	-	203	203	0.03	< 0.005	—	205
Water	_	_	_	_	_	_	_	_	_	0.00	1.11	1.11	< 0.005	< 0.005	_	1.13
Waste	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	12.5	0.38	15.9	0.03	0.40	0.43	0.02	0.10	0.13	0.00	722	722	0.05	0.03	0.73	731
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Mobile	0.03	0.05	0.31	< 0.005	0.07	0.07	< 0.005	0.02	0.02	_	76.0	76.0	< 0.005	< 0.005	0.12	77.3
Area	2.25	0.02	2.58	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	9.64	9.64	< 0.005	< 0.005	_	9.67
Energy	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	33.6	33.6	0.01	< 0.005	_	33.9
Water	_	_	_	_	_	_	_	_	_	0.00	0.18	0.18	< 0.005	< 0.005	_	0.19
Waste	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00
Total	2.28	0.07	2.89	0.01	0.07	0.08	< 0.005	0.02	0.02	0.00	119	119	0.01	< 0.005	0.12	121

# 3. Construction Emissions Details

# 3.1. Demolition (2025) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	_	—	_	—	—	—	—	—	—	—
Daily, Summer (Max)				—	-					—						
Off-Road Equipment	1.25	11.7	11.3	0.48	—	0.48	0.45	—	0.45	—	1,913	1,913	0.08	0.02	—	1,919
Demolitio n	—	—	—	—	0.00	0.00	—	0.00	0.00	—	—	—	—	—	—	—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00

Daily, Winter (Max)		_		_	_		_	—	_	_	_		—		—	_
Off-Road Equipment	1.25	11.7	11.3	0.48	—	0.48	0.45	—	0.45	—	1,913	1,913	0.08	0.02	—	1,919
Demolitio n		-	—	—	0.00	0.00	—	0.00	0.00	—	—	—	—	—	—	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily		—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Off-Road Equipment	0.09	0.80	0.77	0.03	—	0.03	0.03	—	0.03	—	131	131	0.01	< 0.005	—	131
Demolitio n		—	—	—	0.00	0.00	—	0.00	0.00	—	—	—	—	—	—	—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	-	_	-	-	_	-	_	_	-	-	_	—	_	—	_
Off-Road Equipment	0.02	0.15	0.14	0.01	—	0.01	0.01	_	0.01	—	21.7	21.7	< 0.005	< 0.005	_	21.8
Demolitio n	—	-	—	-	0.00	0.00	—	0.00	0.00	—	—	—	—	—	—	—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	—	-		_	_		_			_	_					
Worker	0.03	0.02	0.24	0.00	0.04	0.04	0.00	0.01	0.01	—	45.7	45.7	< 0.005	< 0.005	0.19	46.6
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)																

Worker	0.03	0.02	0.24	0.00	0.04	0.04	0.00	0.01	0.01	—	43.8	43.8	< 0.005	< 0.005	< 0.005	44.5
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Worker	< 0.005	< 0.005	0.02	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	3.02	3.02	< 0.005	< 0.005	0.01	3.07
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	—	_	_	—	_	—	—	—	—	_	_	_	—	_	_
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	0.50	0.50	< 0.005	< 0.005	< 0.005	0.51
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

# 3.2. Demolition (2025) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)			—			_				_						
Off-Road Equipment	1.25	11.7	11.3	0.48	—	0.48	0.45	—	0.45	_	1,913	1,913	0.08	0.02	—	1,919
Demolitio n	—	—	—	—	0.00	0.00	—	0.00	0.00	—	—	—	—	—	—	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)		_	_	—	—	-	_			-				_	_	
Off-Road Equipment	1.25	11.7	11.3	0.48	—	0.48	0.45	_	0.45	_	1,913	1,913	0.08	0.02	—	1,919

Demolitio	—	—	—	—	0.00	0.00	—	0.00	0.00	—	—	—	—	—	—	—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	-	-	-	-	—	—	—	—	—	—	—	—	—		—
Off-Road Equipment	0.09	0.80	0.77	0.03	-	0.03	0.03	—	0.03	—	131	131	0.01	< 0.005		131
Demolitio n	_	-	-	-	0.00	0.00	—	0.00	0.00	—	—	—	—	—		—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	—	_	—	_	_	—	—
Off-Road Equipment	0.02	0.15	0.14	0.01	-	0.01	0.01	_	0.01		21.7	21.7	< 0.005	< 0.005		21.8
Demolitio n		_	_	-	0.00	0.00	_	0.00	0.00		_	_	_	_		_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)		-	-	-	-								_			
Worker	0.03	0.02	0.24	0.00	0.04	0.04	0.00	0.01	0.01	_	45.7	45.7	< 0.005	< 0.005	0.19	46.6
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)		_	_	_	-											
Worker	0.03	0.02	0.24	0.00	0.04	0.04	0.00	0.01	0.01	_	43.8	43.8	< 0.005	< 0.005	< 0.005	44.5
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily		-	-	-	_	—	_	—		—	-		-	—		_

Worker	< 0.005	< 0.005	0.02	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	3.02	3.02	< 0.005	< 0.005	0.01	3.07
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	0.50	0.50	< 0.005	< 0.005	< 0.005	0.51
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00

# 3.3. Site Preparation (2025) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Onsite	—	_	_	_	—	_	_	—	—	_	—	_	_	_	_	—
Daily, Summer (Max)		_	_	_	-	-	-			_		—	—		—	
Daily, Winter (Max)		—	—	_	_	_	—			_		—	—		—	
Off-Road Equipment	1.31 1	12.1	12.1	0.56	—	0.56	0.52	—	0.52	—	2,065	2,065	0.08	0.02	—	2,072
Dust From Material Movement			—	—	6.31	6.31		3.01	3.01	—						
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipment	0.02 1	0.20	0.20	0.01	_	0.01	0.01	_	0.01	-	33.9	33.9	< 0.005	< 0.005	_	34.1

Dust From Material Movement	_	_	_	_	0.10	0.10	_	0.05	0.05	_	_	_	_			
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipment	< 0.005	0.04	0.04	< 0.005	_	< 0.005	< 0.005	-	< 0.005	—	5.62	5.62	< 0.005	< 0.005	_	5.64
Dust From Material Movement				—	0.02	0.02		0.01	0.01							
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)		_	_	_	_	_	_	_				_				_
Daily, Winter (Max)	_	_	_	-	-	_	_	-				_	_			_
Worker	0.03	0.02	0.24	0.00	0.04	0.04	0.00	0.01	0.01	_	43.8	43.8	< 0.005	< 0.005	< 0.005	44.5
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.05	3.45	1.12	0.04	0.60	0.64	0.03	0.17	0.20	_	2,411	2,411	0.13	0.39	0.12	2,530
Average Daily		_	_	_	_	_	-	-		—	—	_	—	—		—
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	0.73	0.73	< 0.005	< 0.005	< 0.005	0.74
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	0.06	0.02	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	—	39.6	39.6	< 0.005	0.01	0.03	41.6
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	0.12	0.12	< 0.005	< 0.005	< 0.005	0.12
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	6.56	6.56	< 0.005	< 0.005	0.01	6.89
## 3.4. Site Preparation (2025) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)		_	_	_	_	_	_		_	_	_				_	_
Daily, Winter (Max)		_	_	_	_	_	_		_	_	_	_	_		_	_
Off-Road Equipment	1.31	12.1	12.1	0.56	—	0.56	0.52	—	0.52	—	2,065	2,065	0.08	0.02	—	2,072
Dust From Material Movement					2.46	2.46		1.17	1.17							
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily		—	—	—	—	—	—	_	—	—	—	—	—	—	—	—
Off-Road Equipment	0.02	0.20	0.20	0.01	-	0.01	0.01	—	0.01	-	33.9	33.9	< 0.005	< 0.005	—	34.1
Dust From Material Movement					0.04	0.04		0.02	0.02							
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipment	< 0.005	0.04	0.04	< 0.005	—	< 0.005	< 0.005		< 0.005	—	5.62	5.62	< 0.005	< 0.005	—	5.64
Dust From Material Movement					0.01	0.01		< 0.005	< 0.005							

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	—	-	—	-	—	—	—	—	—	-	—	—	—	—	—	-
Daily, Summer (Max)	_	_	-	-	-	-	-	-	-	_	-	-	-	-	-	_
Daily, Winter (Max)	_		-	-	-	-	-	-	-	_	—	-	-	-	-	
Worker	0.03	0.02	0.24	0.00	0.04	0.04	0.00	0.01	0.01	-	43.8	43.8	< 0.005	< 0.005	< 0.005	44.5
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.05	3.45	1.12	0.04	0.60	0.64	0.03	0.17	0.20	-	2,411	2,411	0.13	0.39	0.12	2,530
Average Daily	—	—	—	—	—	—	-	—	—	-	—	—	—	-	-	_
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	-	0.73	0.73	< 0.005	< 0.005	< 0.005	0.74
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	0.06	0.02	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	39.6	39.6	< 0.005	0.01	0.03	41.6
Annual	_	_	_	_	_	_	_	_	-	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	0.12	0.12	< 0.005	< 0.005	< 0.005	0.12
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	0.01	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	< 0.005	_	6.56	6.56	< 0.005	< 0.005	0.01	6.89

## 3.5. Grading (2025) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)	_				_	_	_			_					_	_
Daily, Winter (Max)	_		_		_	_	_			_					_	_

Off-Road Equipment	1.51	14.1	14.5	0.64	-	0.64	0.59	-	0.59	-	2,455	2,455	0.10	0.02	-	2,463
Dust From Material Movement	_			_	7.14	7.14	_	3.43	3.43							
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily		-	—	_	-	—	_	—	-	—	—	-	—	—	—	—
Off-Road Equipment	0.05	0.50	0.52	0.02	_	0.02	0.02	—	0.02	—	87.4	87.4	< 0.005	< 0.005	—	87.7
Dust From Material Movement	_	—		_	0.25	0.25	-	0.12	0.12	—	—	_			_	
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	-	—	—	—	-	_	—	—	_	-	—	—	—	—	—
Off-Road Equipment	0.01	0.09	0.09	< 0.005	_	< 0.005	< 0.005	—	< 0.005	-	14.5	14.5	< 0.005	< 0.005	-	14.5
Dust From Material Movement		_		-	0.05	0.05	_	0.02	0.02	_	_					
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	—	_	_
Daily, Summer (Max)	_	—	_	-	_	-	_		—	-	-	—	_		_	_
Daily, Winter (Max)		_	_	_	_	_	_	_	_	_	_	_	_		_	_
Worker	0.04	0.03	0.32	0.00	0.06	0.06	0.00	0.01	0.01	—	58.4	58.4	< 0.005	< 0.005	0.01	59.3
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Hauling	0.14	10.1	3.27	0.13	1.74	1.87	0.08	0.49	0.57	_	7,026	7,026	0.37	1.13	0.35	7,372
Average Daily						—	—	—		—	—	—	—	—	—	—
Worker	< 0.005	< 0.005	0.01	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	2.10	2.10	< 0.005	< 0.005	< 0.005	2.13
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.01	0.36	0.12	< 0.005	0.06	0.07	< 0.005	0.02	0.02	—	250	250	0.01	0.04	0.21	263
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	0.35	0.35	< 0.005	< 0.005	< 0.005	0.35
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	0.07	0.02	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	41.4	41.4	< 0.005	0.01	0.03	43.5

## 3.6. Grading (2025) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	_	_	_	—	—	—	_	_	_	_	_	—
Daily, Summer (Max)																
Daily, Winter (Max)					_									_	_	
Off-Road Equipment	1.51	14.1	14.5	0.64	—	0.64	0.59	—	0.59	—	2,455	2,455	0.10	0.02	—	2,463
Dust From Material Movement					2.78	2.78		1.34	1.34							
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	—	—	—	_	_	—	_	_	_	_	_	—

Off-Road Equipment	0.05	0.50	0.52	0.02	_	0.02	0.02	_	0.02	_	87.4	87.4	< 0.005	< 0.005	—	87.7
Dust From Material Movement		—		_	0.10	0.10	_	0.05	0.05	_	_	_	_			
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	-	-	—	-	-	_	-	—	-	—	—	-	—	—	—
Off-Road Equipment	0.01	0.09	0.09	< 0.005	-	< 0.005	< 0.005	—	< 0.005	—	14.5	14.5	< 0.005	< 0.005	—	14.5
Dust From Material Movement		—	—	_	0.02	0.02	_	0.01	0.01	—	_	_	_	_		
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)		-	-	_	-	-	_	-	-	-	_	_	-	-	_	_
Daily, Winter (Max)		_	_	_	_	_	_	_	_	_	_	_	_			
Worker	0.04	0.03	0.32	0.00	0.06	0.06	0.00	0.01	0.01	-	58.4	58.4	< 0.005	< 0.005	0.01	59.3
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.14	10.1	3.27	0.13	1.74	1.87	0.08	0.49	0.57	_	7,026	7,026	0.37	1.13	0.35	7,372
Average Daily	_	-	—	_	—	—	_	—	—	—	_	_	—	—	—	—
Worker	< 0.005	< 0.005	0.01	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	2.10	2.10	< 0.005	< 0.005	< 0.005	2.13
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.01	0.36	0.12	< 0.005	0.06	0.07	< 0.005	0.02	0.02	_	250	250	0.01	0.04	0.21	263
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	0.35	0.35	< 0.005	< 0.005	< 0.005	0.35

Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	< 0.005	0.07	0.02	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	41.4	41.4	< 0.005	0.01	0.03	43.5

## 3.7. Building Construction (2025) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	-	—	—	—	—	—	-	-	—	—	-	—	—
Daily, Summer (Max)		_				_				_				_		
Daily, Winter (Max)				—										—		
Off-Road Equipment	1.07	8.95	10.0	0.33	—	0.33	0.30	—	0.30	—	1,801	1,801	0.07	0.01	—	1,807
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily		—	—	—	—	—	—	—	—	—	—		_	—	—	
Off-Road Equipment	0.13	1.07	1.20	0.04	—	0.04	0.04	—	0.04	—	215	215	0.01	< 0.005	—	216
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	—	—	—	—	—	—	—	_	_	_	—	—	—	_	—
Off-Road Equipment	0.02	0.19	0.22	0.01	—	0.01	0.01	—	0.01	—	35.6	35.6	< 0.005	< 0.005	—	35.7
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	—	—	—	—	—	—	—	—	_	—	—	—	—	—	—	—
Daily, Summer (Max)		_	_	_		_	_	_		_	_			_	_	

Daily, Winter (Max)	_	_	_	_								_	_	_		-
Worker	0.60	0.43	4.82	0.00	0.87	0.87	0.00	0.20	0.20	—	883	883	0.04	0.04	0.10	896
Vendor	0.05	2.00	0.80	0.02	0.34	0.36	0.02	0.09	0.11	—	1,326	1,326	0.05	0.20	0.09	1,386
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	-
Worker	0.07	0.05	0.57	0.00	0.10	0.10	0.00	0.02	0.02	—	106	106	< 0.005	< 0.005	0.20	108
Vendor	0.01	0.24	0.09	< 0.005	0.04	0.04	< 0.005	0.01	0.01	—	158	158	0.01	0.02	0.18	166
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	—	—	—	—	—	—	—	—	—	—	—	-	—	—	_
Worker	0.01	0.01	0.10	0.00	0.02	0.02	0.00	< 0.005	< 0.005	—	17.6	17.6	< 0.005	< 0.005	0.03	17.9
Vendor	< 0.005	0.04	0.02	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	—	26.2	26.2	< 0.005	< 0.005	0.03	27.4
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00

## 3.8. Building Construction (2025) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)				_	_	_	_	_	_	_	_		_	_	_	_
Daily, Winter (Max)	_	_		_	-	-	-	_	-	_	_		_	_	_	_
Off-Road Equipmen	1.07 1	8.95	10.0	0.33	—	0.33	0.30	—	0.30	—	1,801	1,801	0.07	0.01	—	1,807
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—

Off-Road Equipment	0.13	1.07	1.20	0.04	—	0.04	0.04	—	0.04		215	215	0.01	< 0.005		216
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipment	0.02	0.19	0.22	0.01	-	0.01	0.01	-	0.01	_	35.6	35.6	< 0.005	< 0.005	_	35.7
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	-	—	—	_	_	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)		_	_	-	-	_	-	-	-	-	-	-	-	_	_	_
Daily, Winter (Max)		_	_	-	-	_	-	-	-	-	-	-	-	-	_	_
Worker	0.60	0.43	4.82	0.00	0.87	0.87	0.00	0.20	0.20	_	883	883	0.04	0.04	0.10	896
Vendor	0.05	2.00	0.80	0.02	0.34	0.36	0.02	0.09	0.11	_	1,326	1,326	0.05	0.20	0.09	1,386
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	-	-	_	-	—	_	-	-	-	_	_	_	—	_	_
Worker	0.07	0.05	0.57	0.00	0.10	0.10	0.00	0.02	0.02	—	106	106	< 0.005	< 0.005	0.20	108
Vendor	0.01	0.24	0.09	< 0.005	0.04	0.04	< 0.005	0.01	0.01	—	158	158	0.01	0.02	0.18	166
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	-	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Worker	0.01	0.01	0.10	0.00	0.02	0.02	0.00	< 0.005	< 0.005	—	17.6	17.6	< 0.005	< 0.005	0.03	17.9
Vendor	< 0.005	0.04	0.02	< 0.005	0.01	0.01	< 0.005	< 0.005	< 0.005	_	26.2	26.2	< 0.005	< 0.005	0.03	27.4
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

## 3.9. Building Construction (2026) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	_	_	_	-	_	_	_	—	-	_	_	_	_	_	_
Daily, Summer (Max)		-	-	_		_	_	-	_			_	_	_	-	-
Off-Road Equipment	1.01	8.57	9.96	0.29	—	0.29	0.27	—	0.27	—	1,801	1,801	0.07	0.01	-	1,807
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)		-	-	_		_	_	-	_			_	_	_	-	_
Off-Road Equipment	1.01	8.57	9.96	0.29	—	0.29	0.27	—	0.27	—	1,801	1,801	0.07	0.01	_	1,807
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily		—	—	—	—	—	—	—	—	—	—	—	—	—	_	—
Off-Road Equipment	0.60	5.08	5.90	0.17	—	0.17	0.16	—	0.16	—	1,068	1,068	0.04	0.01	_	1,072
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	—	—	—	—	—		—	—	—	—	—	—	—	—	—
Off-Road Equipment	0.11	0.93	1.08	0.03	—	0.03	0.03	—	0.03	—	177	177	0.01	< 0.005	_	177
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	-	_	_	_	_	-	_	_	-	-	_	_
Daily, Summer (Max)		-	-	-	_	-	-	-	-		_	_	_	_	-	-
Worker	0.59	0.36	4.63	0.00	0.87	0.87	0.00	0.20	0.20	_	905	905	0.03	0.04	3.57	921
Vendor	0.05	1.85	0.74	0.02	0.34	0.36	0.02	0.09	0.11	_	1,301	1,301	0.05	0.19	3.23	1,362
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Daily, Winter (Max)					_					_		_	_	_	_	_
Worker	0.58	0.40	4.52	0.00	0.87	0.87	0.00	0.20	0.20	—	867	867	0.04	0.04	0.09	880
Vendor	0.04	1.90	0.76	0.02	0.34	0.36	0.02	0.09	0.11	—	1,302	1,302	0.05	0.19	0.08	1,359
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Worker	0.34	0.23	2.65	0.00	0.50	0.50	0.00	0.12	0.12	—	518	518	0.02	0.02	0.92	526
Vendor	0.03	1.13	0.44	0.01	0.20	0.21	0.01	0.06	0.07	—	772	772	0.03	0.11	0.83	807
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	-	—	—	—	-	—	—	—	—	—	—	—	—	—	—	-
Worker	0.06	0.04	0.48	0.00	0.09	0.09	0.00	0.02	0.02	—	85.8	85.8	< 0.005	< 0.005	0.15	87.2
Vendor	< 0.005	0.21	0.08	< 0.005	0.04	0.04	< 0.005	0.01	0.01	—	128	128	< 0.005	0.02	0.14	134
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

## 3.10. Building Construction (2026) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)			—	-	_	_	—			_						
Off-Road Equipment	1.01 1	8.57	9.96	0.29	—	0.29	0.27	—	0.27	—	1,801	1,801	0.07	0.01	—	1,807
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)			-	-	-	_	—			_				—		
Off-Road Equipment	1.01 1	8.57	9.96	0.29	_	0.29	0.27	_	0.27	_	1,801	1,801	0.07	0.01	_	1,807

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	-	_	_	—	_	_	—	_	_	-	-	—	—	_
Off-Road Equipmen	0.60 1	5.08	5.90	0.17	—	0.17	0.16	—	0.16	—	1,068	1,068	0.04	0.01	—	1,072
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	_	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Off-Road Equipmen	0.11 1	0.93	1.08	0.03	_	0.03	0.03	—	0.03	_	177	177	0.01	< 0.005	—	177
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	—	-	-	_	_	_	—	-	—	_	-	-	_	—	-	-
Daily, Summer (Max)	-	_	-	-	-	-	-	-	_	-	-	-	-	-	-	-
Worker	0.59	0.36	4.63	0.00	0.87	0.87	0.00	0.20	0.20	_	905	905	0.03	0.04	3.57	921
Vendor	0.05	1.85	0.74	0.02	0.34	0.36	0.02	0.09	0.11	_	1,301	1,301	0.05	0.19	3.23	1,362
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Daily, Winter (Max)		_	_	_	_	-	_	_		_	-	_	_			
Worker	0.58	0.40	4.52	0.00	0.87	0.87	0.00	0.20	0.20	_	867	867	0.04	0.04	0.09	880
Vendor	0.04	1.90	0.76	0.02	0.34	0.36	0.02	0.09	0.11	_	1,302	1,302	0.05	0.19	0.08	1,359
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	-	-	-	-	-	-	—	-	-	-	-	-	-	—
Worker	0.34	0.23	2.65	0.00	0.50	0.50	0.00	0.12	0.12	_	518	518	0.02	0.02	0.92	526
Vendor	0.03	1.13	0.44	0.01	0.20	0.21	0.01	0.06	0.07	_	772	772	0.03	0.11	0.83	807
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	—	_	_	_	_	_	_	_	_	_	_	_	_	—	_

Worker	0.06	0.04	0.48	0.00	0.09	0.09	0.00	0.02	0.02	—	85.8	85.8	< 0.005	< 0.005	0.15	87.2
Vendor	< 0.005	0.21	0.08	< 0.005	0.04	0.04	< 0.005	0.01	0.01	—	128	128	< 0.005	0.02	0.14	134
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00

## 3.11. Paving (2026) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	-	-	-	-	-	-	-	-	-	-	-	-	-	-	_
Daily, Summer (Max)	_	—	—	—	—	-	—	—	—	—	—	—	—	_	—	-
Daily, Winter (Max)		_	_	_	_	_	_	_	_	_	_	_	_		_	-
Off-Road Equipment	0.47 1	4.41	6.48	0.18	—	0.18	0.17	—	0.17	—	991	991	0.04	0.01	—	995
Paving	0.04	—	—	—	—	—	_	_	—	—	—	—	—	—	—	—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Off-Road Equipment	0.03 1	0.24	0.36	0.01	—	0.01	0.01	—	0.01	—	54.3	54.3	< 0.005	< 0.005	—	54.5
Paving	< 0.005	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	_	_	_	—	_	—	—	_	—	—	_	_	—	—	_
Off-Road Equipment	< 0.005	0.04	0.06	< 0.005	—	< 0.005	< 0.005	—	< 0.005	—	8.99	8.99	< 0.005	< 0.005	—	9.02
Paving	< 0.005	_	_	_	_		_	_		_		_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Offsite	_	_	_	_	_	_	_	—	—	_	_	—	—	—	_	—
Daily, Summer (Max)	-	_	_	_	_	_	_	_	_	_	_		_	_	-	
Daily, Winter (Max)	-	_	_	_	_	_	_	_	—	_	_		_	_	_	
Worker	0.05	0.03	0.37	0.00	0.07	0.07	0.00	0.02	0.02	—	71.7	71.7	< 0.005	< 0.005	0.01	72.8
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	_	_	_	—	—	—	_	_	—	_	_	_	—
Worker	< 0.005	< 0.005	0.02	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	3.96	3.96	< 0.005	< 0.005	0.01	4.02
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	—	—	—	_	_	—	_	_	—	—	—	_	—
Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	0.66	0.66	< 0.005	< 0.005	< 0.005	0.67
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

## 3.12. Paving (2026) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)	_					_	—			_	_			—	_	
Daily, Winter (Max)	—		—	—		-	—			_	—			—	—	
Off-Road Equipmen	0.47 1	4.41	6.48	0.18	_	0.18	0.17	—	0.17	_	991	991	0.04	0.01	—	995

Paving	0.04	_	-	-	-	-	-	-	_	_	_	-	_	-	-	-
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	-	-	-	-	-	—	-	-	_	-	—	-	-	-	-
Off-Road Equipment	0.03	0.24	0.36	0.01	—	0.01	0.01	—	0.01	—	54.3	54.3	< 0.005	< 0.005	_	54.5
Paving	< 0.005	_	_	—	—	—	—	_	—	—	—	—	_	—	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	_	—	-	-	-	-	-	_	-	_	-	_	-	-	-
Off-Road Equipment	< 0.005	0.04	0.06	< 0.005	-	< 0.005	< 0.005	-	< 0.005	_	8.99	8.99	< 0.005	< 0.005	-	9.02
Paving	< 0.005	_	_	_	_	-	_	_	_	_	_	-	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)		-	-		-	_		-	_	-	-	_	-	-	-	_
Daily, Winter (Max)		-	-	_	-	_	_	-	_	_	-	_	-	-	-	-
Worker	0.05	0.03	0.37	0.00	0.07	0.07	0.00	0.02	0.02	_	71.7	71.7	< 0.005	< 0.005	0.01	72.8
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	-	—	-	—	—	—	—	-	—	-	—	-	-	-	-
Worker	< 0.005	< 0.005	0.02	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	3.96	3.96	< 0.005	< 0.005	0.01	4.02
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Worker	< 0.005	< 0.005	< 0.005	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	0.66	0.66	< 0.005	< 0.005	< 0.005	0.67
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00

## 3.13. Architectural Coating (2026) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Onsite	_	-	-	-	_	_	—	—	—	_	_	—	_	_	_	—
Daily, Summer (Max)		—	—	—	-	—	—	—	—	_	—		—	—	—	
Daily, Winter (Max)		_	_	_	_	_				_		_	_	_	_	_
Off-Road Equipment	0.12	0.86	1.13	0.02	_	0.02	0.02	—	0.02	_	134	134	0.01	< 0.005	—	134
Architect ural Coatings	209	—	—	—	_	—	_	_	_	—	_	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	-	-	-	-	-	—	—	—	-	—	—	-	—	-	—
Off-Road Equipment	0.01	0.05	0.07	< 0.005	-	< 0.005	< 0.005	—	< 0.005	-	8.10	8.10	< 0.005	< 0.005	-	8.13
Architect ural Coatings	12.7	-	-	-	-	-				-			-		-	
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_
Off-Road Equipment	< 0.005	0.01	0.01	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	1.34	1.34	< 0.005	< 0.005	_	1.35

Architect Coatings	2.31	—	-	—	—	—	—	—	—	—	—	_	_	—	—	—
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)	-	_	_	-	_	_	_	_	-	_	_	_	_	_	_	-
Daily, Winter (Max)	-	_		-				—	-	_	_	_	_	_	_	_
Worker	0.12	0.08	0.90	0.00	0.17	0.17	0.00	0.04	0.04	—	173	173	0.01	0.01	0.02	176
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	-	—	-	—	—	-	-	—	—	-	-	-	_	-	-	-
Worker	0.01	< 0.005	0.05	0.00	0.01	0.01	0.00	< 0.005	< 0.005	_	10.6	10.6	< 0.005	< 0.005	0.02	10.8
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	-	—	—	-	-	-	-	—	_	_	-	-	-	-	-
Worker	< 0.005	< 0.005	0.01	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	1.75	1.75	< 0.005	< 0.005	< 0.005	1.78
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

## 3.14. Architectural Coating (2026) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)	_	_	_	_	_	—			—	_	—		_			

Daily, Winter (Max)		_	_	_	_	_	_	_	—	_	—				—	
Off-Road Equipment	0.12	0.86	1.13	0.02	—	0.02	0.02	_	0.02	_	134	134	0.01	< 0.005	—	134
Architect ural Coatings	41.7	-	-	-	-	-	-	-	_	-	-					
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	—	_	—	_	—	—	—	—	—	—	—	—	—	—	—
Off-Road Equipment	0.01	0.05	0.07	< 0.005	—	< 0.005	< 0.005	—	< 0.005	—	8.10	8.10	< 0.005	< 0.005	—	8.13
Architect ural Coatings	2.53	-	-	_	-	-	_	_		_	_					
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipment	< 0.005	0.01	0.01	< 0.005	_	< 0.005	< 0.005	-	< 0.005	-	1.34	1.34	< 0.005	< 0.005	_	1.35
Architect ural Coatings	0.46	-	-	-	_	-	-	-	_	-	—	_	_	_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Summer (Max)		-	-	-	-	-	-	-	_	-	-					
Daily, Winter (Max)		-	-	_	-	-	-	-		_	_					
Worker	0.12	0.08	0.90	0.00	0.17	0.17	0.00	0.04	0.04	_	173	173	0.01	0.01	0.02	176

Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Worker	0.01	< 0.005	0.05	0.00	0.01	0.01	0.00	< 0.005	< 0.005	—	10.6	10.6	< 0.005	< 0.005	0.02	10.8
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	-	—	—	—	-	—	—	—	—	—	—	—	—	—	—	_
Worker	< 0.005	< 0.005	0.01	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	—	1.75	1.75	< 0.005	< 0.005	< 0.005	1.78
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

# 3.15. Architectural Coating (2027) - Unmitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)				_	_	_				_						
Daily, Winter (Max)				_	_	_				_						
Off-Road Equipment	0.11 1	0.83	1.13	0.02	—	0.02	0.02		0.02	_	134	134	0.01	< 0.005	—	134
Architect ural Coatings	209	—	—	_	_	-			—	_					—	
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	_	_	_	-	-	-	_		_	_	_		_	_	-	

Off-Road Equipment	0.01	0.04	0.06	< 0.005	-	< 0.005	< 0.005	-	< 0.005	-	6.53	6.53	< 0.005	< 0.005	-	6.55
Architect ural Coatings	10.2	_	_	-	-	_	_	_	-	_	-	_	-	_	_	
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Annual	—	-	—	-	—	_	—	-	—	_	—	—	—	-	-	—
Off-Road Equipment	< 0.005	0.01	0.01	< 0.005	—	< 0.005	< 0.005	—	< 0.005	-	1.08	1.08	< 0.005	< 0.005	—	1.09
Architect ural Coatings	1.86		_	-	-	_	_	_	-	_	-	_	-	_	_	
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	-	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	_	-	_	-	_	_	_	_	_	_	_	_	_	-	-	-
Daily, Summer (Max)		_	_	-	-	-	-	-	-	-	-	_	-	_	_	_
Daily, Winter (Max)		_	_	-	-	_	-	_	-	-	-	_	-	_	_	_
Worker	0.11	0.07	0.85	0.00	0.17	0.17	0.00	0.04	0.04	_	170	170	0.01	0.01	0.02	173
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	-	—	—	-	-	—	—	-	—	-	—	—	—	—
Worker	0.01	< 0.005	0.04	0.00	0.01	0.01	0.00	< 0.005	< 0.005	_	8.39	8.39	< 0.005	< 0.005	0.01	8.53
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	—	—	_	_	_	_	_	_	—	_	_	_	_
Worker	< 0.005	< 0.005	0.01	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005		1.39	1.39	< 0.005	< 0.005	< 0.005	1.41
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		0.00	0.00	0.00	0.00	0.00	0.00
---------	------	------	------	------	------	------	------	------	------	--	------	------	------	------	------	------

## 3.16. Architectural Coating (2027) - Mitigated

Location	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Onsite	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Summer (Max)		_	—		—	_	_		_	-				_	_	_
Daily, Winter (Max)										-						
Off-Road Equipment	0.11	0.83	1.13	0.02	—	0.02	0.02	—	0.02	—	134	134	0.01	< 0.005	—	134
Architect ural Coatings	41.7									—						
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	—	—	—	—	—	—	—	—	—	-	—	—	—	—	—	_
Off-Road Equipment	0.01	0.04	0.06	< 0.005	—	< 0.005	< 0.005	—	< 0.005	-	6.53	6.53	< 0.005	< 0.005	—	6.55
Architect ural Coatings	2.04	_	_		_	_	_			-				_	_	_
Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Off-Road Equipment	< 0.005	0.01	0.01	< 0.005	—	< 0.005	< 0.005		< 0.005	-	1.08	1.08	< 0.005	< 0.005	—	1.09
Architect ural Coatings	0.37															

Onsite truck	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	—	0.00	0.00	0.00	0.00	0.00	0.00
Offsite	-	—	-	—	_	-	-	-	-	_	_	—	_	-	-	-
Daily, Summer (Max)	_	_	-	-	—	_	_		-	—	_	-	_	-	_	_
Daily, Winter (Max)	—		_	-	—	—	_		-	—	_	-		-	_	
Worker	0.11	0.07	0.85	0.00	0.17	0.17	0.00	0.04	0.04	-	170	170	0.01	0.01	0.02	173
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Average Daily	-	-	-	—	-	_	-	-	—	-	_	-	-	-	_	-
Worker	0.01	< 0.005	0.04	0.00	0.01	0.01	0.00	< 0.005	< 0.005	_	8.39	8.39	< 0.005	< 0.005	0.01	8.53
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Annual	_	_	_	_	_	_	_	_	-	_	_	_	_	_	_	_
Worker	< 0.005	< 0.005	0.01	0.00	< 0.005	< 0.005	0.00	< 0.005	< 0.005	_	1.39	1.39	< 0.005	< 0.005	< 0.005	1.41
Vendor	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00
Hauling	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	_	0.00	0.00	0.00	0.00	0.00	0.00

# 4. Operations Emissions Details

## 4.1. Mobile Emissions by Land Use

4.1.1. Unmitigated

		· · · · · ·					<b>\</b>				/					
Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e

Daily, Summer (Max)		—	—		_		_			_		_		_	_	
User Defined Educationa	0.22 al	0.28	2.07	0.01	0.48	0.48	< 0.005	0.12	0.13		550	550	0.02	0.02	1.98	559
Total	0.22	0.28	2.07	0.01	0.48	0.48	< 0.005	0.12	0.13	—	550	550	0.02	0.02	1.98	559
Daily, Winter (Max)			—		_		_			_		_	_	_		
User Defined Educationa	0.22 al	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13		533	533	0.02	0.02	0.05	541
Total	0.22	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	—	533	533	0.02	0.02	0.05	541
Annual	—	—	—	—	—		—			—	—	—	—	—		—
User Defined Educationa	0.03 al	0.05	0.31	< 0.005	0.07	0.07	< 0.005	0.02	0.02	_	76.0	76.0	< 0.005	< 0.005	0.12	77.3
Total	0.03	0.05	0.31	< 0.005	0.07	0.07	< 0.005	0.02	0.02	_	76.0	76.0	< 0.005	< 0.005	0.12	77.3

## 4.1.2. Mitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)																
User Defined Educationa	0.22 al	0.28	2.07	0.01	0.48	0.48	< 0.005	0.12	0.13		550	550	0.02	0.02	1.98	559
Total	0.22	0.28	2.07	0.01	0.48	0.48	< 0.005	0.12	0.13	—	550	550	0.02	0.02	1.98	559
Daily, Winter (Max)			_	_	_	_	_	_								

User Defined Educationa	0.22 al	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13		533	533	0.02	0.02	0.05	541
Total	0.22	0.30	2.00	0.01	0.48	0.48	< 0.005	0.12	0.13	—	533	533	0.02	0.02	0.05	541
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
User Defined Educationa	0.03 al	0.05	0.31	< 0.005	0.07	0.07	< 0.005	0.02	0.02		76.0	76.0	< 0.005	< 0.005	0.12	77.3
Total	0.03	0.05	0.31	< 0.005	0.07	0.07	< 0.005	0.02	0.02	_	76.0	76.0	< 0.005	< 0.005	0.12	77.3

## 4.2. Energy

## 4.2.1. Electricity Emissions By Land Use - Unmitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	—	—	—	-	—	—	—	-	-	—	—	—	—	-	-
User Defined Educationa	—	_	_	_	_	_	—	_	_	_	203	203	0.03	< 0.005	_	205
Total	_	—	_	—	—	—	_	—	—	—	203	203	0.03	< 0.005	—	205
Daily, Winter (Max)				—	_	—			—	_	—		—		_	_
User Defined Educationa	—				_	_	—		_	_	203	203	0.03	< 0.005	_	205
Total	—	—	—	—	-	—	—	—	—	—	203	203	0.03	< 0.005	-	205
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	-	-
User Defined Educationa		_	_	_	-	-		—	-	_	33.6	33.6	0.01	< 0.005	_	33.9
Total	—	—	—	—	—	—	—	—	—	—	33.6	33.6	0.01	< 0.005	—	33.9

### 4.2.2. Electricity Emissions By Land Use - Mitigated

### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)		—	_	-	-	-	—	_	_	_	_	_	-	_	-	_
User Defined Educationa	— al	_	_	_	_	_	_	_	_	_	203	203	0.03	< 0.005	_	205
Total	—	—	—	—	—	—	—	—	—	_	203	203	0.03	< 0.005	—	205
Daily, Winter (Max)		_	-	-	-	-	_	-	-	_	_	-	-	-	-	-
User Defined Educationa	—	—	-	-	-	_		-	_	_	203	203	0.03	< 0.005	_	205
Total	—	-	-	_	—	-	—	-	-	—	203	203	0.03	< 0.005	-	205
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
User Defined Educationa	— al		—	_	_	_		—	_	_	33.6	33.6	0.01	< 0.005	_	33.9
Total	_	_	_	_	_	_	_	_	_	_	33.6	33.6	0.01	< 0.005	_	33.9

### 4.2.3. Natural Gas Emissions By Land Use - Unmitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)			-			-										
User Defined Educationa	0.00 al	0.00	0.00	0.00		0.00	0.00		0.00	—	0.00	0.00	0.00	0.00		0.00
Total	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	_	0.00

Daily, Winter (Max)	_	—	—	—		—	—	 		—	—	—	—	—	
User Defined Educationa	0.00 al	0.00	0.00	0.00		0.00	0.00	 0.00		0.00	0.00	0.00	0.00		0.00
Total	0.00	0.00	0.00	0.00	—	0.00	0.00	 0.00	—	0.00	0.00	0.00	0.00	—	0.00
Annual		—	—	—	—	—	—	 	—	—		—	—		—
User Defined Educationa	0.00 al	0.00	0.00	0.00		0.00	0.00	 0.00		0.00	0.00	0.00	0.00		0.00
Total	0.00	0.00	0.00	0.00	_	0.00	0.00	 0.00	—	0.00	0.00	0.00	0.00		0.00

## 4.2.4. Natural Gas Emissions By Land Use - Mitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	—	—	—	—	_	—	—	—	—	—	—	—	—	—	—
User Defined Educationa	0.00 al	0.00	0.00	0.00	_	0.00	0.00		0.00	_	0.00	0.00	0.00	0.00	_	0.00
Total	0.00	0.00	0.00	0.00	—	0.00	0.00	—	0.00	—	0.00	0.00	0.00	0.00	—	0.00
Daily, Winter (Max)					_	_				_	_				_	
User Defined Educationa	0.00 al	0.00	0.00	0.00	_	0.00	0.00		0.00	-	0.00	0.00	0.00	0.00		0.00
Total	0.00	0.00	0.00	0.00	—	0.00	0.00	—	0.00	—	0.00	0.00	0.00	0.00	—	0.00
Annual	—	—	—	—	—	_	—	—	—	—	—	—	—	—	—	—
User Defined Educationa	0.00 al	0.00	0.00	0.00	-	0.00	0.00		0.00	_	0.00	0.00	0.00	0.00	_	0.00

Total	0.00	0.00	0.00	0.00	_	0.00	0.00	_	0.00	_	0.00	0.00	0.00	0.00	—	0.00
-------	------	------	------	------	---	------	------	---	------	---	------	------	------	------	---	------

## 4.3. Area Emissions by Source

### 4.3.1. Unmitigated

Source	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	—	—	—	-	—	—	—	—	_	—	—	—	—	—	—
Consume r Products	7.70			_	_		_	_		_		_	_	_	_	
Architect ural Coatings	2.29	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Landscap e Equipme nt	2.57	0.13	15.7	0.03		0.03	0.02		0.02		64.4	64.4	< 0.005	< 0.005		64.6
Total	12.6	0.13	15.7	0.03	-	0.03	0.02	—	0.02	-	64.4	64.4	< 0.005	< 0.005	—	64.6
Daily, Winter (Max)	-	-	-	_	-	-	_		_	-	_	_	_		_	_
Consume r Products	7.70				_					_						
Architect ural Coatings	2.29				_					_						
Total	9.99	—	—	—	—	—	—	—	—	-	—	—	—	—	—	—
Annual	_	_	_		_	_	_	_		_	_	_	_		_	_
Consume r Products	1.41				_					_						

Architect Coatings	0.42	—	—	—	—		—			—	—	—	—	—	—	—
Landscap e Equipme nt	0.42	0.02	2.58	< 0.005	_	< 0.005	< 0.005		< 0.005		9.64	9.64	< 0.005	< 0.005		9.67
Total	2.25	0.02	2.58	< 0.005	—	< 0.005	< 0.005	—	< 0.005	—	9.64	9.64	< 0.005	< 0.005	—	9.67

## 4.3.2. Mitigated

Source	ROG	NOx	CO	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_	_	_	_	_	_	—	—		—	_	—	—	_	_
Consume r Products	7.70										—					
Architect ural Coatings	2.29										—					
Landscap e Equipme nt	2.57	0.13	15.7	0.03		0.03	0.02		0.02		64.4	64.4	< 0.005	< 0.005		64.6
Total	12.6	0.13	15.7	0.03	—	0.03	0.02	_	0.02	—	64.4	64.4	< 0.005	< 0.005	—	64.6
Daily, Winter (Max)			—						_		_	_				
Consume r Products	7.70		_					_	_		—	_				
Architect ural Coatings	2.29		_	_			_	_	_		_	_				
Total	9.99	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Annual	—	—	—	—	—	—	—	_	—	—	—	—	—	—	—	—
Consume r Products	1.41														_	
Architect ural Coatings	0.42							_			—	—			—	—
Landscap e Equipme nt	0.42	0.02	2.58	< 0.005		< 0.005	< 0.005	_	< 0.005		9.64	9.64	< 0.005	< 0.005	_	9.67
Total	2.25	0.02	2.58	< 0.005	_	< 0.005	< 0.005	_	< 0.005	_	9.64	9.64	< 0.005	< 0.005	_	9.67

## 4.4. Water Emissions by Land Use

## 4.4.1. Unmitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)					_	—								—		
User Defined Educationa	—				-	_				0.00	1.11	1.11	< 0.005	< 0.005		1.13
Total	—	—	—	—	—	—	—	—	—	0.00	1.11	1.11	< 0.005	< 0.005	—	1.13
Daily, Winter (Max)					—	-								-		
User Defined Educationa	—			—	—	—				0.00	1.11	1.11	< 0.005	< 0.005		1.13
Total	_	_	_	—	_	_	_	_	_	0.00	1.11	1.11	< 0.005	< 0.005	_	1.13
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

User Defined Educationa					—	 —		—	0.00	0.18	0.18	< 0.005	< 0.005	—	0.19
Total	—	—	—	—	—	 	—		0.00	0.18	0.18	< 0.005	< 0.005	—	0.19

### 4.4.2. Mitigated

### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)		—				—	—	—	—				—		—	—
User Defined Educationa	— al	_	_					—	_	0.00	1.11	1.11	< 0.005	< 0.005		1.13
Total	—	—	—	—	—	—	—	—	—	0.00	1.11	1.11	< 0.005	< 0.005	—	1.13
Daily, Winter (Max)				—	—						—					
User Defined Educationa	 al									0.00	1.11	1.11	< 0.005	< 0.005		1.13
Total	—	—	—	—	—	—	—	—	—	0.00	1.11	1.11	< 0.005	< 0.005	—	1.13
Annual	—	—	—	—	—	—	—	—	—	—	—	—	-	—	—	—
User Defined Educationa	— al	—			-	_	_		—	0.00	0.18	0.18	< 0.005	< 0.005		0.19
Total		_		_	_	_	_			0.00	0.18	0.18	< 0.005	< 0.005		0.19

## 4.5. Waste Emissions by Land Use

#### 4.5.1. Unmitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e

Daily, Summer (Max)	—	_		—	—	_	_	_				_	—		_	_
User Defined Educationa	 al						_			0.00	0.00	0.00	0.00	0.00		0.00
Total	—	—	—	—	—	—	—		—	0.00	0.00	0.00	0.00	0.00	—	0.00
Daily, Winter (Max)							—									
User Defined Educationa	 al									0.00	0.00	0.00	0.00	0.00		0.00
Total	—	—	—	—	—	—	—		—	0.00	0.00	0.00	0.00	0.00	—	0.00
Annual	—	—	—	—	—	—	—		—	—	—	—	—	_	—	—
User Defined Educationa	 al									0.00	0.00	0.00	0.00	0.00		0.00
Total	_	_	_	_	_	_	_		_	0.00	0.00	0.00	0.00	0.00	_	0.00

## 4.5.2. Mitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)						—										
User Defined Educationa	 al	_	_	_	-	-	_	_		0.00	0.00	0.00	0.00	0.00	_	0.00
Total	—	—	—	—	—	—	—	—	—	0.00	0.00	0.00	0.00	0.00	—	0.00
Daily, Winter (Max)		_	_			—				_					_	

User Defined Educationa	 al								_	0.00	0.00	0.00	0.00	0.00		0.00
Total	—	—	—	—	—	—	—	—	—	0.00	0.00	0.00	0.00	0.00	—	0.00
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
User Defined Educationa	 al									0.00	0.00	0.00	0.00	0.00		0.00
Total	_	_	_	_	_	_	_	_	_	0.00	0.00	0.00	0.00	0.00	_	0.00

## 4.6. Refrigerant Emissions by Land Use

#### 4.6.1. Unmitigated

### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	_	-	-	-	-	-	-	-	-	-	-	_	—	_	_
Total	—	-	_	—	—	—	—	—	—	—	—	—	-	—	-	_
Daily, Winter (Max)	_	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total	—	-	-	-	—	—	-	—	-	-	-	-	-	-	-	-
Annual	—	-	_	_	_	_	_	_	_	_	_	_	-	_	-	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

### 4.6.2. Mitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	—	—	-	-	-	-	-	—	—	—	_	—	_	—	—

Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Winter (Max)																
Total	—	—	—	_	—	—	—	—				—	—	—	—	—
Annual	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Total	—	_	—	_	—	_	_	_	_	_	_	—	—	—	—	—

## 4.7. Offroad Emissions By Equipment Type

### 4.7.1. Unmitigated

### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Equipme nt Type	ROG	NOx	СО	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	_	—	_	-	_	_	_	—	_	-	—	_	_	-	-
Total	—	-	—	—	—	—	—	—	—	—	—	—	-	—	—	—
Daily, Winter (Max)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Total	-	-	-	-	_	_	_	_	_	_	_	_	-	-	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

### 4.7.2. Mitigated

Equipme	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
nt																
Туре																

Daily, Summer (Max)				_	_					_	_	_			_	_
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	_
Daily, Winter (Max)				_	_					_	_				_	_
Total	—	—	—	—	—	—	—		—	—	—	_		—	—	_
Annual	_	_	_	_	_		—		_	_	_	_		_	_	_
Total	—	—	—	—	—	—	—		—	—	—	—		—	—	_

## 4.8. Stationary Emissions By Equipment Type

#### 4.8.1. Unmitigated

#### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Equipme nt Type	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)		—	—		-				—							
Total	—	—	—	—	-	—	—	—	—	—	—	—	-	—	—	—
Daily, Winter (Max)	_	_	_	_	—	_	_	_	_			_	_	_	_	
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

#### 4.8.2. Mitigated

Equipme nt	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)					_											
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Winter (Max)																
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_
Total	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

## 4.9. User Defined Emissions By Equipment Type

## 4.9.1. Unmitigated

Equipme nt Type	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	—		—	_	_	_	_	_	_					—	—
Total	—	—	—	—	-	—	—	—	—	—	_	—	—	—	—	—
Daily, Winter (Max)					_	_	_								_	_
Total	-	-	—	-	-	—	—	—	—	—	—	—	—	-	-	-
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Total	_	_	_	_	_	_	_	—	_	_	—	_	—	_	_	_

Equipme nt Type	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	_	_					_	_		—	_	_	—	_	—	_
Total	_	—	—	—	—	—	—	_	—	—	_	_	_	—	—	—
Daily, Winter (Max)							—	_		—		_	_		—	_
Total	—	—	_	_	—	_	—	_	_	—	—	_	_	—	—	—
Annual	_	_		_	_	_	_	_		_	_	_	_	_	_	_
Total	_				_		—	_			_	_			_	—

#### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

## 4.10. Soil Carbon Accumulation By Vegetation Type

## 4.10.1. Soil Carbon Accumulation By Vegetation Type - Unmitigated

Vegetatio n	ROG	NOx	CO	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)				—												
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Winter (Max)				_	—					_	_			_		
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Annual	_	_	_	_	_	_	_	_	_	_	_	_	—	_	_	_
Total	_	_	_	_	—	_	_	_	_	—	—	—	—	_	—	_

#### 4.10.2. Above and Belowground Carbon Accumulation by Land Use Type - Unmitigated

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)			—	—	—				-							_
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Winter (Max)		_		—	-		-		-							
Total	—	—	—	—	—	_	—	—	—	—	—	—	—	—	—	—
Annual	—	-	—	—	-	_	—	—	-	—	—	—	—	-	—	—
Total	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_

#### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

#### 4.10.3. Avoided and Sequestered Emissions by Species - Unmitigated

Species	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	СО2Т	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	-	-	-	-	-	-	-	-	-	—		—	—	-	—
Avoided	—	—	—	—	—	—	-	—	—	—	—	—	—	—	-	-
Subtotal	-	_	_	_	—	_	_	_	_	_	_	—	_	_	-	_
Sequeste red	—	-	-	-	-	—	—	_	—	—	-	—	-	-	-	—
Subtotal	_	_	_	_	_	_	_	_	_	_	_	—	_	_	-	_
Removed	-	_	_	_	—	_	_	_	-	-	_	—	—	_	-	_
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_
Daily, Winter (Max)	_	_	-	-	-	-	-	-	-	-	-		_	_	_	—
Avoided	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
-----------------	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---	---
Subtotal	—	—	—	—	—	—	—	—	—	_	—	—	—	—	—	—
Sequeste red		—	—	—	—		—		—	—	—		—	—	—	—
Subtotal	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Removed	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Subtotal	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
—	—	—	—	—	—	—	—	—	—	—	—	_	—	—	—	—
Annual	_	—	—	—	—	—	—	—	—	—	—	_	—	—	—	—
Avoided	_	—	—	—	—	—	—	—	—	—	—	_	—	—	—	—
Subtotal	_	—	—	—	—	—	—	—	—	—	—	_	—	—	—	—
Sequeste red		—	—	—	—		—		—	—			—	—	—	—
Subtotal	_	—	—	—	—	—	—	—	—	—	—	_	—	—	—	—
Removed	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_
Subtotal		_	_	—			_		_	_			_	_	—	—
		_	—	—	_		_	_	_	_	_		_	_	_	_

### 4.10.4. Soil Carbon Accumulation By Vegetation Type - Mitigated

# Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Vegetatio n	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)			-	-	-	-	-	-	-	-						_
Total	—	—	—	—	—	_	—	—	_	_	—	—	—	—	—	_
Daily, Winter (Max)		—	—	—	—	_	—	—	_	_	—		—		—	_
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Annual	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_	_

Total	_	_	_	_	_	_	—	—	 —	_	 _	_	_	_

#### 4.10.5. Above and Belowground Carbon Accumulation by Land Use Type - Mitigated

#### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Land Use	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	—	—	—	—	—	—	—	—	-	—	—			—	
Total	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Daily, Winter (Max)		—	—	—	-	-				_						
Total	—	-	—	—	-	—	—	—	—	-	—	-	—	—	—	—
Annual	_	-	-	_	_	_	-	—	-	_	—	_	_	_	_	—
Total	—	—	—	—	—	—	—	—	—	_	—	—	—	—	—	—

#### 4.10.6. Avoided and Sequestered Emissions by Species - Mitigated

#### Criteria Pollutants (lb/day for daily, ton/yr for annual) and GHGs (lb/day for daily, MT/yr for annual)

Species	ROG	NOx	со	PM10E	PM10D	PM10T	PM2.5E	PM2.5D	PM2.5T	BCO2	NBCO2	CO2T	CH4	N2O	R	CO2e
Daily, Summer (Max)	—	—	—	—	-	—			—	_	—	—	—	—	—	—
Avoided	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Subtotal	—	—	—	-	_	—	—	—	—	-	—	—	—	—	—	—
Sequeste red	—	—	—	-	-	—	—	_	—	—	—	—	—	—	—	—
Subtotal	—	—	—	-	_	—	—	—	—	-	—	—	—	—	—	—
Removed	—	—	—	-	_	—	—	—	—	-	—	—	-	—	—	—
Subtotal	_	_	_	_	_	_	_	_	_	_	_	_	_		_	_
_	_	_	_	_	_	_	_	_	_	_		_	_	_	_	_

Daily, Winter (Max)		_	_	_								_	_	_	_	_
Avoided	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Subtotal	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Sequeste red	—	—	—	—	—	—	—		—	—	—	—	—	—	—	—
Subtotal	—	—	—	—	—	—	—	—		—	—	—	—	—	—	—
Removed	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Subtotal	—	-	—	—	—	—	—	—	—	—	—	—	—	—	—	—
_	_	_	_	_	_	_	—	_	_	_	_	_	_	—	—	—
Annual	—	-	—	—	_	—	—	—	—	—	—	_	—	—	—	—
Avoided	—	-	—	—	_	—	—	—	—	—	—	—	—	—	—	—
Subtotal	—	-	—	—	—	—	—	—	—	—	—	—	—	—	—	—
Sequeste red	—	—	—	—	—	—	—		—	—	—		—	—	—	—
Subtotal	—	-	—	—	_	—	—	—	—	—	—	—	—	—	—	—
Removed	_	_	_	_	_	_	_	_	_	_	_		_	_	_	_
Subtotal	_	_	_	_	_	_	_		_	_	_		_	_	_	—
_	_	_	_	_	_	_	_		_	_	_	_	_	_	_	_

# 5. Activity Data

# 5.1. Construction Schedule

Phase Name	Phase Type	Start Date	End Date	Days Per Week	Work Days per Phase	Phase Description
Demolition	Demolition	9/1/2025	10/3/2025	5.00	25.0	—
Site Preparation	Site Preparation	10/4/2025	10/13/2025	5.00	6.00	—
Grading	Grading	10/14/2025	10/30/2025	5.00	13.0	—
Building Construction	Building Construction	11/1/2025	10/30/2026	5.00	260	_

Paving	Paving	11/3/2026	11/30/2026	5.00	20.0	—
Architectural Coating	Architectural Coating	12/1/2026	1/25/2027	5.00	40.0	—

# 5.2. Off-Road Equipment

# 5.2.1. Unmitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Demolition	Tractors/Loaders/Back hoes	Diesel	Average	1.00	8.00	84.0	0.37
Demolition	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Demolition	Concrete/Industrial Saws	Diesel	Average	1.00	8.00	33.0	0.73
Site Preparation	Graders	Diesel	Average	1.00	8.00	148	0.41
Site Preparation	Rubber Tired Dozers	Diesel	Average	1.00	7.00	367	0.40
Site Preparation	Tractors/Loaders/Back hoes	Diesel	Average	1.00	8.00	84.0	0.37
Grading	Graders	Diesel	Average	1.00	8.00	148	0.41
Grading	Tractors/Loaders/Back hoes	Diesel	Average	2.00	7.00	84.0	0.37
Grading	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Building Construction	Cranes	Diesel	Average	1.00	6.00	367	0.29
Building Construction	Forklifts	Diesel	Average	1.00	6.00	82.0	0.20
Building Construction	Generator Sets	Diesel	Average	1.00	8.00	14.0	0.74
Building Construction	Tractors/Loaders/Back hoes	Diesel	Average	1.00	6.00	84.0	0.37
Building Construction	Welders	Diesel	Average	3.00	8.00	46.0	0.45
Paving	Tractors/Loaders/Back hoes	Diesel	Average	1.00	8.00	84.0	0.37
Paving	Pavers	Diesel	Average	1.00	6.00	81.0	0.42
Paving	Paving Equipment	Diesel	Average	1.00	8.00	89.0	0.36

Paving	Rollers	Diesel	Average	1.00	7.00	36.0	0.38
Paving	Cement and Mortar Mixers	Diesel	Average	1.00	6.00	10.0	0.56
Architectural Coating	Air Compressors	Diesel	Average	1.00	6.00	37.0	0.48

# 5.2.2. Mitigated

Phase Name	Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor
Demolition	Tractors/Loaders/Back hoes	Diesel	Average	1.00	8.00	84.0	0.37
Demolition	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Demolition	Concrete/Industrial Saws	Diesel	Average	1.00	8.00	33.0	0.73
Site Preparation	Graders	Diesel	Average	1.00	8.00	148	0.41
Site Preparation	Rubber Tired Dozers	Diesel	Average	1.00	7.00	367	0.40
Site Preparation	Tractors/Loaders/Back hoes	Diesel	Average	1.00	8.00	84.0	0.37
Grading	Graders	Diesel	Average	1.00	8.00	148	0.41
Grading	Tractors/Loaders/Back hoes	Diesel	Average	2.00	7.00	84.0	0.37
Grading	Rubber Tired Dozers	Diesel	Average	1.00	8.00	367	0.40
Building Construction	Cranes	Diesel	Average	1.00	6.00	367	0.29
Building Construction	Forklifts	Diesel	Average	1.00	6.00	82.0	0.20
Building Construction	Generator Sets	Diesel	Average	1.00	8.00	14.0	0.74
Building Construction	Tractors/Loaders/Back hoes	Diesel	Average	1.00	6.00	84.0	0.37
Building Construction	Welders	Diesel	Average	3.00	8.00	46.0	0.45
Paving	Tractors/Loaders/Back hoes	Diesel	Average	1.00	8.00	84.0	0.37
Paving	Pavers	Diesel	Average	1.00	6.00	81.0	0.42
Paving	Paving Equipment	Diesel	Average	1.00	8.00	89.0	0.36
Paving	Rollers	Diesel	Average	1.00	7.00	36.0	0.38

Paving	Cement and Mortar Mixers	Diesel	Average	1.00	6.00	10.0	0.56
Architectural Coating	Air Compressors	Diesel	Average	1.00	6.00	37.0	0.48

# 5.3. Construction Vehicles

### 5.3.1. Unmitigated

Phase Name	Тгір Туре	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Demolition	—	—	—	—
Demolition	Worker	7.50	8.10	LDA,LDT1,LDT2
Demolition	Vendor	_	6.90	HHDT,MHDT
Demolition	Hauling	0.00	20.0	HHDT
Demolition	Onsite truck			HHDT
Site Preparation	_			_
Site Preparation	Worker	7.50	8.10	LDA,LDT1,LDT2
Site Preparation	Vendor	_	6.90	HHDT,MHDT
Site Preparation	Hauling	33.0	20.0	HHDT
Site Preparation	Onsite truck	_	_	HHDT
Grading	_	_	_	_
Grading	Worker	10.0	8.10	LDA,LDT1,LDT2
Grading	Vendor	_	6.90	HHDT,MHDT
Grading	Hauling	96.2	20.0	HHDT
Grading	Onsite truck			HHDT
Building Construction				_
Building Construction	Worker	151	8.10	LDA,LDT1,LDT2
Building Construction	Vendor	59.0	6.90	HHDT,MHDT
Building Construction	Hauling	0.00	20.0	HHDT
Building Construction	Onsite truck	_	_	HHDT
Paving		_	_	_

Paving	Worker	12.5	8.10	LDA,LDT1,LDT2
Paving	Vendor	—	6.90	HHDT,MHDT
Paving	Hauling	0.00	20.0	HHDT
Paving	Onsite truck	_	_	HHDT
Architectural Coating	_	—	—	_
Architectural Coating	Worker	30.2	8.10	LDA,LDT1,LDT2
Architectural Coating	Vendor	_	6.90	HHDT,MHDT
Architectural Coating	Hauling	0.00	20.0	HHDT
Architectural Coating	Onsite truck	—	—	HHDT

# 5.3.2. Mitigated

Phase Name	Тгір Туре	One-Way Trips per Day	Miles per Trip	Vehicle Mix
Demolition	_	_	_	—
Demolition	Worker	7.50	8.10	LDA,LDT1,LDT2
Demolition	Vendor	_	6.90	HHDT,MHDT
Demolition	Hauling	0.00	20.0	HHDT
Demolition	Onsite truck	_		HHDT
Site Preparation	_	_	_	_
Site Preparation	Worker	7.50	8.10	LDA,LDT1,LDT2
Site Preparation	Vendor	_	6.90	HHDT,MHDT
Site Preparation	Hauling	33.0	20.0	HHDT
Site Preparation	Onsite truck			HHDT
Grading	_	_	_	_
Grading	Worker	10.0	8.10	LDA,LDT1,LDT2
Grading	Vendor	_	6.90	HHDT,MHDT
Grading	Hauling	96.2	20.0	HHDT
Grading	Onsite truck	_	_	HHDT
Building Construction		_	_	_

Building Construction	Worker	151	8.10	LDA,LDT1,LDT2
Building Construction	Vendor	59.0	6.90	HHDT,MHDT
Building Construction	Hauling	0.00	20.0	HHDT
Building Construction	Onsite truck	_	_	HHDT
Paving	_	_	_	_
Paving	Worker	12.5	8.10	LDA,LDT1,LDT2
Paving	Vendor	—	6.90	HHDT,MHDT
Paving	Hauling	0.00	20.0	HHDT
Paving	Onsite truck	_	_	HHDT
Architectural Coating	_	_	_	_
Architectural Coating	Worker	30.2	8.10	LDA,LDT1,LDT2
Architectural Coating	Vendor	_	6.90	HHDT,MHDT
Architectural Coating	Hauling	0.00	20.0	HHDT
Architectural Coating	Onsite truck	—	—	HHDT

### 5.4. Vehicles

#### 5.4.1. Construction Vehicle Control Strategies

Non-applicable. No control strategies activated by user.

# 5.5. Architectural Coatings

Phase Name	Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
Architectural Coating	0.00	0.00	540,000	180,000	—

# 5.6. Dust Mitigation

### 5.6.1. Construction Earthmoving Activities

Phase Name	Material Imported (Ton of Debris)	Material Exported (Ton of Debris)	Acres Graded (acres)	Material Demolished (sq. ft.)	Acres Paved (acres)
Demolition	0.00	0.00	0.00	—	_
Site Preparation	2,000	_	5.63	0.00	_
Grading	10,000	_	13.0	0.00	_
Paving	0.00	0.00	0.00	0.00	0.30

#### 5.6.2. Construction Earthmoving Control Strategies

Control Strategies Applied	Frequency (per day)	PM10 Reduction	PM2.5 Reduction
Water Demolished Area	2	36%	36%

# 5.7. Construction Paving

Land Use	Area Paved (acres)	% Asphalt
User Defined Educational	0.30	100%

# 5.8. Construction Electricity Consumption and Emissions Factors

#### kWh per Year and Emission Factor (lb/MWh)

Year	kWh per Year	CO2	CH4	N2O
2025	0.00	204	0.03	< 0.005
2026	0.00	204	0.03	< 0.005
2027	0.00	204	0.03	< 0.005

# 5.9. Operational Mobile Sources

#### 5.9.1. Unmitigated

Land Use Type	Trips/Weekday	Trips/Saturday	Trips/Sunday	Trips/Year	VMT/Weekday	VMT/Saturday	VMT/Sunday	VMT/Year
User Defined Educational	36.0	36.0	0.00	11,263	675	675	0.00	211,214
66 / 77								

#### 5.9.2. Mitigated

Land Use Type	Trips/Weekday	Trips/Saturday	Trips/Sunday	Trips/Year	VMT/Weekday	VMT/Saturday	VMT/Sunday	VMT/Year
User Defined Educational	36.0	36.0	0.00	11,263	675	675	0.00	211,214

# 5.10. Operational Area Sources

#### 5.10.1. Hearths

### 5.10.1.1. Unmitigated

#### 5.10.1.2. Mitigated

#### 5.10.2. Architectural Coatings

Residential Interior Area Coated (sq ft)	Residential Exterior Area Coated (sq ft)	Non-Residential Interior Area Coated (sq ft)	Non-Residential Exterior Area Coated (sq ft)	Parking Area Coated (sq ft)
0	0.00	540,000	180,000	—

### 5.10.3. Landscape Equipment

Season	Unit	Value
Snow Days	day/yr	0.00
Summer Days	day/yr	330

### 5.10.4. Landscape Equipment - Mitigated

Season	Unit	Value
Snow Days	day/yr	0.00
Summer Days	day/yr	330

### 5.11. Operational Energy Consumption

#### 5.11.1. Unmitigated

#### Electricity (kWh/yr) and CO2 and CH4 and N2O and Natural Gas (kBTU/yr)

Land Use	Electricity (kWh/yr)	CO2	CH4	N2O	Natural Gas (kBTU/yr)
User Defined Educational	363,102	204	0.0330	0.0040	0.00

#### 5.11.2. Mitigated

#### Electricity (kWh/yr) and CO2 and CH4 and N2O and Natural Gas (kBTU/yr)

Land Use	Electricity (kWh/yr)	CO2	CH4	N2O	Natural Gas (kBTU/yr)
User Defined Educational	363,102	204	0.0330	0.0040	0.00

### 5.12. Operational Water and Wastewater Consumption

#### 5.12.1. Unmitigated

Land Use	Indoor Water (gal/year)	Outdoor Water (gal/year)	
User Defined Educational	0.00	515,451	

#### 5.12.2. Mitigated

Land Use	Indoor Water (gal/year)	Outdoor Water (gal/year)
User Defined Educational	0.00	515,451

### 5.13. Operational Waste Generation

#### 5.13.1. Unmitigated

Land Use	Waste (ton/year)	Cogeneration (kWh/year)
User Defined Educational	0.00	_

#### 5.13.2. Mitigated

Land Use	Waste (ton/year)	Cogeneration (kWh/year)
User Defined Educational	0.00	_

# 5.14. Operational Refrigeration and Air Conditioning Equipment

#### 5.14.1. Unmitigated

Land Use Type	Equipment Type	Refrigerant	GWP	Quantity (kg)	Operations Leak Rate	Service Leak Rate	Times Serviced
5 14 2 Mitigated							
5.14.2. Miligaleu							
Land Use Type	Equipment Type	Refrigerant	GWP	Quantity (kg)	Operations Leak Rate	Service Leak Rate	Times Serviced

### 5.15. Operational Off-Road Equipment

#### 5.15.1. Unmitigated

Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor

#### 5.15.2. Mitigated

Equipment Type	Fuel Type	Engine Tier	Number per Day	Hours Per Day	Horsepower	Load Factor

### 5.16. Stationary Sources

#### 5.16.1. Emergency Generators and Fire Pumps

Equipment Type	Fuel Type	Number per Day	Hours per Day	Hours per Year	Horsepower	Load Factor
5.16.2. Process Boile	ers					

	Equipment Type	Fuel Type	Number	Boiler Rating (MMBtu/hr)	Daily Heat Input (MMBtu/day)	Annual Heat Input (MMBtu/yr)
--	----------------	-----------	--------	--------------------------	------------------------------	------------------------------

# 5.17. User Defined

Equipment Type		Fuel Type		
5.18. Vegetation				
5.18.1. Land Use Change				
5.18.1.1. Unmitigated				
Vegetation Land Use Type	Vegetation Soil Type	Initial Acres		Final Acres
5.18.1.2. Mitigated				
Vegetation Land Use Type	Vegetation Soil Type	Initial Acres		Final Acres
5.18.1. Biomass Cover Type				
5.18.1.1. Unmitigated				
Biomass Cover Type	Initial Acres		Final Acres	
5.18.1.2. Mitigated				
Biomass Cover Type	Initial Acres		Final Acres	
5.18.2. Sequestration				

# 5.18.2.1. Unmitigated

Tree Type Number Electricity Saved (kWh/year) Natural Gas Saved (btu/year)	Тгее Туре	Number	Electricity Saved (kWh/year)	Natural Gas Saved (btu/year)
--	-----------	--------	------------------------------	------------------------------

5.18.2.2. Mitigated

Tree Type

Number

Electricity Saved (kWh/year)

Natural Gas Saved (btu/year)

# 6. Climate Risk Detailed Report

### 6.1. Climate Risk Summary

Cal-Adapt midcentury 2040–2059 average projections for four hazards are reported below for your project location. These are under Representation Concentration Pathway (RCP) 8.5 which assumes GHG emissions will continue to rise strongly through 2050 and then plateau around 2100.

Climate Hazard	Result for Project Location	Unit
Temperature and Extreme Heat	6.73	annual days of extreme heat
Extreme Precipitation	7.35	annual days with precipitation above 20 mm
Sea Level Rise	_	meters of inundation depth
Wildfire	50.5	annual hectares burned

Temperature and Extreme Heat data are for grid cell in which your project are located. The projection is based on the 98th historical percentile of daily maximum/minimum temperatures from observed historical data (32 climate model ensemble from Cal-Adapt, 2040–2059 average under RCP 8.5). Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi. Extreme Precipitation data are for the grid cell in which your project are located. The threshold of 20 mm is equivalent to about ¾ an inch of rain, which would be light to moderate rainfall if received over a full day or heavy rain if received over a period of 2 to 4 hours. Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

Sea Level Rise data are for the grid cell in which your project are located. The projections are from Radke et al. (2017), as reported in Cal-Adapt (Radke et al., 2017, CEC-500-2017-008), and consider inundation location and depth for the San Francisco Bay, the Sacramento-San Joaquin River Delta and California coast resulting different increments of sea level rise coupled with extreme storm events. Users may select from four scenarios to view the range in potential inundation depth for the grid cell. The four scenarios are: No rise, 0.5 meter, 1.0 meter, 1.41 meters Wildfire data are for the grid cell in which your project are located. The projections are from UC Davis, as reported in Cal-Adapt (2040–2059 average under RCP 8.5), and consider historical data of climate, vegetation, population density, and large (> 400 ha) fire history. Users may select from four model simulations to view the range in potential wildfire probabilities for the grid cell. The four simulations make different assumptions about expected rainfall and temperature are: Warmer/drier (HadGEM2-ES), Cooler/wetter (CNRM-CM5), Average conditions (CanESM2), Range of different rainfall and temperature possibilities (MIROC5). Each grid cell is 6 kilometers (km) by 6 km, or 3.7 miles (mi) by 3.7 mi.

### 6.2. Initial Climate Risk Scores

Climate Hazard	Exposure Score	Sensitivity Score	Adaptive Capacity Score	Vulnerability Score
Temperature and Extreme Heat	N/A	N/A	N/A	N/A
Extreme Precipitation	N/A	N/A	N/A	N/A
Sea Level Rise	N/A	N/A	N/A	N/A
Wildfire	1	0	0	N/A

Flooding	N/A	N/A	N/A	N/A
Drought	0	1	0	N/A
Snowpack Reduction	N/A	N/A	N/A	N/A
Air Quality Degradation	N/A	N/A	N/A	N/A

The sensitivity score reflects the extent to which a project would be adversely affected by exposure to a climate hazard. Exposure is rated on a scale of 1 to 5, with a score of 5 representing the greatest exposure.

The adaptive capacity of a project refers to its ability to manage and reduce vulnerabilities from projected climate hazards. Adaptive capacity is rated on a scale of 1 to 5, with a score of 5 representing the greatest ability to adapt.

The overall vulnerability scores are calculated based on the potential impacts and adaptive capacity assessments for each hazard. Scores do not include implementation of climate risk reduction measures.

### 6.3. Adjusted Climate Risk Scores

Climate Hazard	Exposure Score	Sensitivity Score	Adaptive Capacity Score	Vulnerability Score
Temperature and Extreme Heat	N/A	N/A	N/A	N/A
Extreme Precipitation	N/A	N/A	N/A	N/A
Sea Level Rise	N/A	N/A	N/A	N/A
Wildfire	1	1	1	2
Flooding	N/A	N/A	N/A	N/A
Drought	1	1	1	2
Snowpack Reduction	N/A	N/A	N/A	N/A
Air Quality Degradation	N/A	N/A	N/A	N/A

The sensitivity score reflects the extent to which a project would be adversely affected by exposure to a climate hazard. Exposure is rated on a scale of 1 to 5, with a score of 5 representing the greatest exposure.

The adaptive capacity of a project refers to its ability to manage and reduce vulnerabilities from projected climate hazards. Adaptive capacity is rated on a scale of 1 to 5, with a score of 5 representing the greatest ability to adapt.

The overall vulnerability scores are calculated based on the potential impacts and adaptive capacity assessments for each hazard. Scores include implementation of climate risk reduction measures.

### 6.4. Climate Risk Reduction Measures

# 7. Health and Equity Details

# 7.1. CalEnviroScreen 4.0 Scores

Indicator	Result for Project Census Tract
Exposure Indicators	
AQ-Ozone	14.9
AQ-PM	9.16
AQ-DPM	13.2
Drinking Water	83.2
Lead Risk Housing	13.7
Pesticides	55.0
Toxic Releases	12.0
Traffic	78.5
Effect Indicators	
CleanUp Sites	0.00
Groundwater	39.4
Haz Waste Facilities/Generators	74.7
Impaired Water Bodies	23.9
Solid Waste	52.9
Sensitive Population	_
Asthma	0.11
Cardio-vascular	2.08
Low Birth Weights	_
Socioeconomic Factor Indicators	_
Education	_
Housing	99.9
Linguistic	17.3
Poverty	99.9
Unemployment	96.3

The maximum CalEnviroScreen score is 100. A high score (i.e., greater than 50) reflects a higher pollution burden compared to other census tracts in the state.

# 7.2. Healthy Places Index Scores

The maximum Health Blasse Index sears is 100 A high sears (i.e.	areater than EO) reflects healthier community conditions compared to other concust tracts in the state
THE MAXIMUM REALT FIACES MUEX SCOLE IS TOU. A MUM SCOLE (I.E.)	
	, g

Indicator	Result for Project Census Tract
Economic	_
Above Poverty	
Employed	_
Median HI	_
Education	_
Bachelor's or higher	_
High school enrollment	_
Preschool enrollment	_
Transportation	_
Auto Access	
Active commuting	_
Social	
2-parent households	
Voting	_
Neighborhood	
Alcohol availability	
Park access	_
Retail density	_
Supermarket access	_
Tree canopy	_
Housing	_
Homeownership	_
Housing habitability	
Low-inc homeowner severe housing cost burden	
Low-inc renter severe housing cost burden	

Uncrowded housing	—
Health Outcomes	
Insured adults	
Arthritis	0.0
Asthma ER Admissions	99.8
High Blood Pressure	0.0
Cancer (excluding skin)	0.0
Asthma	0.0
Coronary Heart Disease	0.0
Chronic Obstructive Pulmonary Disease	0.0
Diagnosed Diabetes	0.0
Life Expectancy at Birth	0.0
Cognitively Disabled	88.7
Physically Disabled	99.5
Heart Attack ER Admissions	99.8
Mental Health Not Good	0.0
Chronic Kidney Disease	0.0
Obesity	0.0
Pedestrian Injuries	0.0
Physical Health Not Good	0.0
Stroke	0.0
Health Risk Behaviors	
Binge Drinking	0.0
Current Smoker	0.0
No Leisure Time for Physical Activity	0.0
Climate Change Exposures	
Wildfire Risk	0.6
SLR Inundation Area	0.0

Children	99.4
Elderly	99.8
English Speaking	0.0
Foreign-born	0.0
Outdoor Workers	62.0
Climate Change Adaptive Capacity	
Impervious Surface Cover	92.1
Traffic Density	0.0
Traffic Access	0.0
Other Indices	
Hardship	0.0
Other Decision Support	
2016 Voting	0.0

### 7.3. Overall Health & Equity Scores

Metric	Result for Project Census Tract
CalEnviroScreen 4.0 Score for Project Location (a)	33.0
Healthy Places Index Score for Project Location (b)	
Project Located in a Designated Disadvantaged Community (Senate Bill 535)	No
Project Located in a Low-Income Community (Assembly Bill 1550)	Yes
Project Located in a Community Air Protection Program Community (Assembly Bill 617)	No

a: The maximum CalEnviroScreen score is 100. A high score (i.e., greater than 50) reflects a higher pollution burden compared to other census tracts in the state. b: The maximum Health Places Index score is 100. A high score (i.e., greater than 50) reflects healthier community conditions compared to other census tracts in the state.

#### 7.4. Health & Equity Measures

No Health & Equity Measures selected.

### 7.5. Evaluation Scorecard

Health & Equity Evaluation Scorecard not completed.

# 7.6. Health & Equity Custom Measures

No Health & Equity Custom Measures created.

# 8. User Changes to Default Data

Screen	Justification
Land Use	Site size is 1.3 acres. Building would be ~2 stories and 36,000 sf
Construction: Construction Phases	Adjusted to match Cal Poly timeframes
Construction: Off-Road Equipment	Site size limits the number of loaders in Phase 1. There is also no building demo. Just pavement removal.
Construction: Paving	Some repaving along site frontage would be necessary
Operations: Vehicle Data	Student center would serve on-campus student residents. Trips would be limited to staff. Assumed no more than 18 employees per day.